

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
CENTRAL VALLEY REGION

ORDER NO. 93-031

WASTE DISCHARGE REQUIREMENTS
FOR

FRANK ANDRE AND ROBERT HOURET
dba SAN LUIS PARTNERSHIP
MERCED COUNTY

The California Regional Water Quality Control Board, Central Valley Region, (hereafter Board) finds that:

1. Frank Andre and Robert Houret, dba San Luis Partnership (hereafter Discharger), submitted a Report of Waste Discharge, dated 21 August 1992, for a wastewater treatment facility. The property is owned by San Luis Partnership.
2. The Discharger proposes to build a wastewater collection, treatment, and disposal system, which will provide sewerage service to the San Luis Hills housing development, San Luis Truck Plaza, and an undeveloped four-acre parcel within the project boundaries. The Truck Plaza consists of a restaurant, hotel, and truck wash. The four-acre parcel is to be developed at a later date.
3. San Luis Partnership is the developer of the truck plaza. John Costanzo and Bob Houret are the developers of San Luis Hills. Bob Houret owns the undeveloped four-acre parcel.
4. The Discharger will use treated wastewater to spray irrigate 8 acres of landscape around the facility and 31 acres of undeveloped land to the east of the San Luis Hills housing development. The land to be spray irrigated is within the project boundaries and owned by the Discharger. San Luis Truck Plaza will use treated wastewater for flushing toilets.
5. Upon completion of construction, San Luis Water District will become owner and operator of the facility. San Luis Water District will gain ownership of the facility property as well. At that time San Luis Water District will petition to the Board for a modification of these waste discharge requirements to reflect the change in ownership.
6. The wastewater treatment facility is at the intersections of Gonzaga and Santa Nella Roads, Merced County, in Section 20, T10S, R9E, MDB&M, as shown in Attachment A, which is attached hereto and made part of the Order by reference.
7. The treatment system is a staged trickling filter system with a design average daily flow rate of 52,000 gpd, and a maximum daily flow rate of 75,000 gpd. The facility process includes screening, flow equalization, primary clarification, trickling filtration and secondary clarification, followed by chemical addition, filtration, and disinfection. Treated effluent will be stored in a lined pond prior to reuse.

8. The characteristic of the treated wastewater as described in the Report of Waste Discharge is:

<u>Constituents</u>	<u>Concentrations</u>
BOD ₅	20 mg/l
Total Suspended Solids	20 mg/l
Total Coliform	<2.2 MPN/100/ml
Total Dissolved Solids	550 mg/l
Turbidity	<2 NTU

9. The Board adopted a Water Quality Control Plan, Second Edition, for the San Joaquin River Basin (hereafter Basin Plan), which contains water quality objectives for all waters of the Basin. These requirements implement the Basin Plan.
10. Ephemeral streams near the facility are tributaries to the San Joaquin River. Streams near the facility support no aquatic habitat. The beneficial uses of the San Joaquin River are municipal, industrial, and agricultural supply; recreation; aesthetic enjoyment; ground water recharge; fresh water replenishment; and preservation and enhancement of fish, wildlife, and other aquatic resources.
11. The beneficial uses of underlying ground water are industrial and agricultural supply.
12. The California Department of Health Services has established statewide reclamation criteria in Title 22, California Code of Regulations, Section 60301, et seq. (hereafter Title 22) for the use of reclaimed water has developed guidelines for specific uses. These uses are consistent with those guidelines.
13. Merced County Planning Department has certified a final negative declaration in accordance with the California Environmental Quality Act (CEQA) (Public Resources Code Section 21000, et seq.) and the State CEQA Guidelines. The project as approved will not have a significant effect on water quality.
14. This discharge is exempt from the requirements of Title 23, CCR, Section 2510, et seq. (hereafter Chapter 15). The exemption, pursuant to Section 2511(b), is based on the following:
- The Board is issuing waste discharge requirements, and
 - The discharge complies with the Basin Plan, and
 - The wastewater does not need to be managed according to 22 CCR, Division 4, Chapter 30, as a hazardous waste.

15. The Board has notified the Discharger and interested agencies and persons of its intent to prescribe waste discharge requirements for this discharge and has provided them with an opportunity for a public hearing and an opportunity to submit their written views and recommendations.
16. The Board, in a public meeting, heard and considered all comments pertaining to the discharge.

IT IS HEREBY ORDERED that Frank Andre and Robert Houret, dba San Luis Partnership, its agents, successors, and assigns, in order to meet the provisions contained in Division 7 of the California Water Code and regulations adopted thereunder, shall comply with the following:

A. Discharge Prohibitions:

1. Discharge of wastes to surface waters or surface water drainage courses is prohibited.
2. Bypass or overflow of untreated or partially treated waste is prohibited.
3. Discharge of waste classified as 'hazardous' or 'designated', as defined in Sections 2521(a) and 2522(a) of Chapter 15, is prohibited.
4. Grazing of milking animals within the area irrigated with effluent is prohibited.

B. Discharge Specifications:

1. The average dry weather discharge flow shall not exceed 0.052 mgd.
2. The maximum daily discharge shall not exceed 0.075 mgd.
3. Objectionable odors originating at this facility shall not be perceivable beyond the limits of the wastewater treatment and disposal areas.
4. As a means of discerning compliance with Discharge Specification No. 3, the dissolved oxygen content in the upper zone (1 foot) of wastewater in ponds shall not be less than 1.0 mg/l.
5. The treatment facilities shall be designed, constructed, operated, and maintained to prevent inundation or washout due to floods with a 100-year return frequency.
6. The effluent from the treatment facility shall not exceed the following limits:

<u>Constituent</u>	<u>Units</u>	<u>Monthly Average</u>	<u>Daily Maximum</u>
BOD ₅ ¹	mg/l	20	40
Settleable Solids	ml/l	0.2	0.5
Coliform	MPN/100 ml	2.2 Median	23
Turbidity	NTU	2	5

¹ Five-day, 20° Celsius biochemical oxygen demand.

7. Treatment plant effluent shall not have a pH less than 6.5 or greater than 8.5.
8. There shall be no standing water in the disposal area 48-hours after wastewater is applied.
9. Ponds shall be managed to prevent breeding of mosquitos. In particular,
 - a. An erosion control program should assure that small coves and irregularities are not created around the perimeter of the water surface.
 - b. Weeds shall be minimized through control of water depth, harvesting, or herbicides.
 - c. Dead algae, vegetation, and debris shall not accumulate on the water surface.
10. Public contact with undisinfected wastewater shall be precluded through such means as fences, signs, and other acceptable alternatives.
11. Ponds shall have sufficient capacity to accommodate allowable wastewater flow and design seasonal precipitation and ancillary inflow and infiltration during the nonirrigation season. Design seasonal precipitation shall be based on total annual precipitation using a return period of 100 years, distributed monthly in accordance with historical rainfall patterns. Freeboard shall never be less than two feet (measured vertically).

13. Areas irrigated with reclaimed water shall be managed to prevent breeding of mosquitos. More specifically,
 - a. Tail water must be returned and all applied irrigation water must infiltrate completely within a 48-hour period.
 - b. Ditches not serving as wildlife habitat should be maintained free of emergent, marginal, and floating vegetation.
 - c. Low-pressure and unpressurized pipelines and ditches accessible to mosquitos shall not be used to store reclaimed water.
14. Reclaimed water for irrigation shall be managed to minimize erosion, runoff, and movement of aerosols from the disposal area.
15. Direct or windblown spray shall be confined to the designated reclamation area and prevented from contacting drinking water facilities.
16. The Discharger may not spray irrigate effluent during periods of precipitation and for at least 24 hours after cessation of precipitation, or when winds exceed 30 mph.
17. Signs with proper wording of sufficient size shall be placed at areas of access and around the perimeter of all areas used for effluent disposal to alert the public of the use of reclaimed water.
18. Stormwater runoff from the irrigation field shall not be discharged to any surface water drainage course within 48-hours of the last application of reclaimed water.
19. Application of reclaimed wastewater to the reclamation area shall be at reasonable rates considering the crop, soil, climate, and irrigation management system. The nutrient loading of the reclamation area, including the nutritive value of organic and chemical fertilizers and of the reclaimed water, shall not exceed the crop demand.
20. There shall be no irrigation or impoundment of reclaimed water within 500 feet of any domestic water well or within 100 feet of any irrigation well unless it is demonstrated to the satisfaction of the Executive Officer that less distance is justified.

C. Sludge Disposal:

1. Collected screenings, sludges, and other solids removed from liquid wastes shall be disposed of in a manner that is consistent with Chapter 15 and approved by the Executive Officer.
2. Any proposed change in sludge use or disposal practice shall be reported to the Executive Officer at least 90 days in advance of the change.
3. The Discharger is encouraged to comply with the State Guidance Manual issued by the Department of Health Services titled *Manual of Good Practice for Landspreading of Sewage Sludge*.

D. Ground Water Limitations:

The discharge, in combination with other sources, shall not cause underlying ground water to:

1. Contain waste constituents in concentrations statistically greater than receiving water limits, where specified below, or background water quality where not specified.
2. Contain chemicals, heavy metals, or trace elements in concentrations that adversely affect beneficial uses or exceed maximum contaminant levels specified in 22 CCR, Division 4, Chapter 15.
3. Exceed a most probable number of total coliform organisms of 2.2/100 ml over any seven-day period.
4. Exceed concentrations of radionuclides specified in 22 CCR, Division 4, Chapter 15.
5. Contain taste or odor-producing substances in concentrations that cause nuisance or adversely affect beneficial uses.
6. Contain concentrations of chemical constituents in amounts that adversely affect agricultural use.

E. Provisions:

1. The Discharger shall not allow pollutant-free wastewater to be discharged into the collection, treatment, and disposal system in amounts that significantly diminish the system's capability to comply with this Order. Pollutant-free wastewater means rainfall,

ground water, cooling waters, and condensates that are essentially free of pollutants.

2. The Discharger shall use the best practical cost-effective control technique currently available to limit mineralization to no more than a reasonable increment.
3. The Discharger shall implement the necessary legal authorities, programs, and controls to ensure that the following incompatible wastes are not introduced to the treatment system, where incompatible wastes are:
 - a. Wastes which create a fire or explosion hazard in the treatment works;
 - b. Wastes which will cause corrosive structural damage to treatment works, but in no case wastes with a pH lower than 5.0, unless the works is specially designed to accommodate such wastes;
 - c. Solid or viscous wastes in amounts which cause obstruction to flow in sewers, or which cause other interference with proper operation or treatment works;
 - d. Any waste, including oxygen demanding pollutants (BOD, etc.), released in such volume or strength as to cause inhibition or disruption in the treatment works, and subsequent treatment process upset and loss of treatment efficiency;
 - e. Heat in amounts that inhibit or disrupt biological activity in the treatment works, or that raise influent temperatures above 40°C (104°F), unless the treatment works is designed to accommodate such heat.
 - f. Petroleum oil, nonbiodegradable cutting oil, or products of mineral oil origin in amounts that will cause interference or pass through;
 - g. Pollutants which result in the presence of toxic gases, vapors, or fumes within the treatment works in a quantity that may cause acute worker health and safety problems; and
 - h. Any trucked or hauled pollutants, except at points predesignated by the Discharger.
4. For the purposes of this Order, "spray irrigation" means application of reclaimed water to crops by sprinklers.

5. Reclaimed water controllers, valves, etc., shall be affixed with reclaimed water warning signs, and these and quick couplers and sprinkler heads shall be of a type, or secured in a manner, that permits operation by authorized personnel only.
6. Supplementing reclaimed water by connection with a domestic drinking water source or irrigation or industrial wells requires an air gap device.
7. A contingency plan, including notification of the Board and health agencies and outlining action to be taken when effluent quality fails to meet required standards, shall be submitted **within 60 days** of adoption of this Order.
8. A report on using reclaimed water for toilet flushing will be submitted to the Board **within 60 days** of adoption of this Order. The report will include, but is not limited to, measures to be taken to prevent cross contamination of domestic water supplies with reclaimed water and procedures of notifying employees and the public of the use of reclaimed water and precautions that should be taken.
9. If the Discharger intends to use reclaimed water on crops other than those specified in an accepted land management plan, it shall first submit a written report demonstrating, to the satisfaction of the Executive Officer, that management of reclaimed water and irrigated properties will assure compliance with the terms of this Order.
10. The Discharger shall comply with the Monitoring and Reporting Program No. 93-031, which is part of this Order, and any revisions thereto as ordered by the Executive Officer.
11. The Discharger shall comply with the "Standard Provisions and Reporting Requirements for Waste Discharge Requirements", dated 1 March 1991, which are attached hereto and by reference a part of this Order. This attachment and its individual paragraphs are commonly referenced as "Standard Provision(s)."
12. In the event of any change in control or ownership of land or waste discharge facilities described herein, the Discharger shall notify the succeeding owner or operator of the existence of this Order by letter, a copy of which shall be immediately forwarded to this office.
13. At least **90 days** prior to termination or expiration of any lease, contract, or agreement involving disposal or reclamation areas or off-site reuse of effluent, used to justify the capacity authorized

herein and assure compliance with this Order, the Discharger shall notify the Board in writing of the situation and of what measures have been taken or are being taken to assure full compliance with this Order.

14. The Discharger shall use the best practicable cost-effective control technique currently available to comply with salinity limits specified in this order.
15. The Discharger must comply with all conditions of this Order, including timely submittal of technical and monitoring reports as directed by the Executive Officer. Violations may result in enforcement action, including Regional Board or court orders requiring corrective action or imposing civil monetary liability, or in revision or rescission of this Order.
16. A copy of this Order shall be kept at the discharge facility for reference by operating personnel. Key operating personnel shall be familiar with its contents.
17. If reclaimed water is used for construction purposes, it shall comply with the most current edition of "Guidelines for Use of Reclaimed Water for Construction Purposes". Other uses of reclaimed water not specifically authorized herein shall be subject to the approval of the Executive Officer and shall comply with 22 CCR, Division 4.
18. The Board will review this Order periodically and will revise requirements when necessary.

I, WILLIAM H. CROOKS, Executive Officer, do hereby certify the foregoing is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, Central Valley Region, on 26 February 1993.


WILLIAM H. CROOKS, Executive Officer

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
CENTRAL VALLEY REGION

MONITORING AND REPORTING PROGRAM NO. 93-031

FOR

FRANK ANDRE AND ROBERT HOURET
dba SAN LUIS PARTNERSHIP
MERCED COUNTY

Specific sample station locations shall be established under direction of the Board's staff and a description of the stations shall be attached to this Order.

EFFLUENT MONITORING

Effluent samples shall be collected just prior to discharge to the disposal facility. Effluent samples should be representative of the volume and nature of the discharge. Samples collected from the outlet structure of ponds will be considered adequately composited. Time of collection of a grab sample shall be recorded. Effluent monitoring shall include at least the following:

<u>Constituents</u>	<u>Units</u>	<u>Type of Sample</u>	<u>Sampling Frequency</u>
20°C BOD	mg/l	24-hour Comp	Weekly
Suspended Matter	mg/l	24-hour Comp	Weekly
Settleable Matter	ml/l	24-hour Comp	Weekly
Nitrates as N	mg/l	24-hour Comp	Monthly
Total Dissolved Solids	mg/l	24-hour Comp	Quarterly
Electric Conductivity	μmhos/cm	24-hour Comp	Weekly
pH	pH Units	24-hour Comp	Weekly
Total Coliform Organisms	MPN/100 ml	Grab	Weekly
Flow	mgd	Continuous	Daily
Turbidity	NTU	24-hour Comp	Daily
Oil & Grease	mg/l	Grab	Monthly

SLUDGE MONITORING

A composite sample of sludge shall be collected annually in accordance with EPAs *POTW Sludge Sampling and Analysis Guidance Document, August 1989*, and tested for the following metals:

Cadmium	Lead
Chromium	Nickel
Copper	Zinc

Sampling records shall be retained for a minimum of a five years. A log shall be kept of sludge quantities generated and of handling and disposal activities. The frequency of entries is discretionary; however, the log should be complete enough to serve as a basis for part of the annual report.

WATER SUPPLY MONITORING

A sampling station shall be established where a representative sample of the municipal water supply can be obtained. Water supply monitoring shall include at least the following:

<u>Constituents</u>	<u>Units</u>	<u>Sampling Frequency</u>
Electrical Conductivity @ 25oC	μ mhos/cm	Annual

ANNUAL LAND MANAGEMENT REPORTS

The Discharger shall submit a summary report on the land management operation after the conclusion of each season. The report shall discuss total water application over the season; the total volume of wastewater applied; the total nutrient loading from wastewater, sludges, and chemical fertilizers; and amount of nutrients removed through harvest of the crop. In short, the report shall present a mass balance relative to pollutants of concern and hydraulic loading. The report is due by 30 January of the following year.

REPORTING

In reporting the monitoring data, the Discharger shall arrange the data in tabular form so that the date, the constituents, and the concentrations are readily discernible. The data shall be summarized in such a manner to illustrate clearly the compliance with waste discharge requirements.

Monthly monitoring reports shall be submitted to the Regional Board by the 20th day of the following month.


MONITORING AND REPORTING PROGRAM
FRANK ANDRE AND ROBERT HOURET
dba SAN LUIS PARTNERSHIP
MERCED COUNTY

-3-

The results of any monitoring done more frequently than required at the locations specified in the Monitoring and Reporting Program shall be reported to the Board.

Upon written request of the Board, the Discharger shall submit a report to the Board by **30 January** of each year. The report shall contain both tabular and graphical summaries of the monitoring data obtained during the previous year. In addition, the Discharger shall discuss the compliance record and the corrective actions taken or planned which may be needed to bring the discharge into full compliance with the waste discharge requirements.

The Discharger shall implement the above monitoring program as of the date of this Order.



WILLIAM H. CROOKS, Executive Officer

26 February 1993

(Date)

MKK

INFORMATION SHEET


FRANK ANDRE AND ROBERT HOURET
dba SAN LUIS PARTNERSHIP
MERCED COUNTY

This wastewater treatment facility is being built to provide sewerage service to a new subdivision of approximately 60 homes and commercial property at the intersection of Gonzaga and Santa Nella Roads in Merced County. The commercial property consists of a restaurant, motel, truck wash and gas station (all of which are still to be constructed). After construction of the facility is completed, San Luis Water District will take over as owner and operator of the plant.

The treatment system is a staged trickling filter with secondary clarification, chemical addition, filtration, and disinfection. Wastewater will be discharged to a holding pond with ultimate disposal through spray irrigation of 8 acres of landscaping and 31 acres of undeveloped land. Portions of the area to be irrigated will have a high degree of public contact. The eight acres of landscaping will be a buffer zone for the treatment plant. This tertiary treatment will meet the effluent standards required by Title 22 for reclamation purposes.

The facility will have a maximum daily discharge of 0.075 mgd and an average monthly discharge of 0.052 mgd. Surface water in the vicinity of the facility is limited to ephemeral streams which are tributary to the San Joaquin River.

ATTACHMENT A



SCALE: 1" = 200'

—'AGRICULTURE'—

WASTE WATER TREATMENT PLANT
EFFLUENT STORAGE BASIN

152

[illegible]

33

U.S.A.
- DEPT. OF INTERIOR -

ELVIS

-P.G.& E. SUB-STATION-

EXIST.
-RECREATIONAL VEHICLE PARK-

ATTACHMENT B

- WASTE DISCHARGE PLAN -
SAN LUIS HILLS
AND
SAN LUIS PLAZA

BEING A SUBDIVISION OF PARCELS
AS SHOWN ON THE "PARCEL MAP FOR DONN B. CAMPION,"
BOOK 69, PARCEL MAP, PAGES 38-39,
MEMPHIS COUNTY RECORDS,
SECTION 20 T. 10 S., R. 9 E., M.D.B.M.

APN 78-100-33

Q. HHS / WASHPH UNIT
JOB NO 910704
06-25-92 MEM

P. 4-11-11 11
20 PM 10

~AGRICULTURE~

--AGRICULTURE--

SPRAYFIELD

BAL
- surveying
- engineering

BEDESEN-CARDOZA-ANDREWS, Inc.
777 W. 32nd St., P.O. Box 392
Morced, California 95340
(209) 722-0042

WASTE WATER TREATMENT PLANT
EFFLUENT STORAGE BASIN

251

Highway

ELVIS

U.S.A.
-- DEPT. OF INTERIOR --

-P.G.A. E. SUB-STATION-

EXIST.
-RECREATIONAL VEHICLE PARK-

2 PM 00

—AGRICULTURE—

BBAL

BEDSEN-CARDOZA-ANDREWS, Inc.
777 W. 22nd St., P.O. Box 391
Morced, California 95340
(209) 722-6642

-AGRICULTURE-

SPRAYFIELD

**- WASTE DISCHARGE PLAN -
SAN LUIS HILLS
AND
SAN LUIS PLAZA**

BEING A SUBDIVISION OF PARCELS
AS SHOWN ON THE "PARCEL MAP FOR DONN B. CAMPION,"
BOOK 69, PARCEL MAPS, PAGES 38-39,
MENARD COUNTY RECORDS.

APR 70-140-25

0. \MAILS\MAILS\PM LISTS
JOB NO 8116700
04-25-92 PM

95 JUN - 9 AM 10: 37

RECEIVED
FRESNO
CVRWQOB