

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
CENTRAL VALLEY REGION

ORDER NO. 5-00-025

WASTE DISCHARGE REQUIREMENTS

FOR
CITY OF SAN JOSE
SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

The California Regional Water Quality Control Board, Central Valley Region, (hereafter Board) finds that:

1. On 10 June 1999, the City of San Jose, San Jose Family Camp, (hereafter Discharger) submitted a Report of Waste Discharge to discharge its treated wastewater to land. Supplemental information was submitted on 16 July 1999. The wastewater treatment and disposal facilities are owned and operated by the Discharger.
2. San Jose Family Camp is at 11401 Cherry Lake Road, off Highway 120, approximately half way between the town of Groveland and Buck Meadow. The wastewater treatment and disposal facilities are in Section 28, T1S, R18E, MDB&M, with surface water drainage to the Middle Fork Tuolumne River as shown in Attachment A, which is attached hereto and made part of the Order by reference.
3. Order No. 75-109, adopted by the Board on 23 May 1975, prescribes requirements for an aerated pond and discharge by means of a sprayfield. This Order is neither adequate nor consistent with current plans and policies of the Board.
4. A fire, which burned through the camp in August 1999, destroyed certain components of the wastewater system. Plans are being prepared for reconstruction of the destroyed system components before the 2000 camp season. It is anticipated that the system design will remain essentially the same as it has been in the past.
5. San Jose Family Camp occupies approximately 40.25 acres of a 200-acre parcel (APN # 068-130-12) deeded to USDA Forest Service. Camp facilities include tent platform camping, a dining hall, a water system, recreational facilities, playgrounds, parking, utility buildings, and sanitary facilities and a sewage treatment system. Approximately two thousand campers per year are accommodated, and a part-time seasonal manager and volunteers operate the camp. During the off-season, from October through May, the facility is occupied only by a caretaker.
6. The camp is in operation only on a seasonal basis, typically from June through September when a maximum of 300 persons could occupy the camp. Although the facility does not currently contain a flow meter, flow volumes were originally estimated not to exceed 10,550 gallons per day (gpd) but by all reports, the average flow volume has never exceeded or approached that value. Wastewater from the Camp is collected in a six foot diameter by twelve-foot deep wet well and is pumped from this lift station to the oxidation pond. The lift station has had a dual

pump and controller system, high water alarm, and a two thousand-gallon overflow reserve storage tank capacity provided by two concrete septic tanks. The pump and controller system were destroyed by the recent fire. It is anticipated that they will be replaced by components similar to those which existed previously. Both the wet well and the overflow septic tanks are within twenty feet of the perennial stream, which flows through the Camp. There is no reported history of pump failure or overflow. The oxidation pond is approximately 20,000 square feet in area and has a total depth of approximately fifteen feet. The oxidation pond has mechanical aeration and has an operating volume of 0.795 million gallons (at 12.75 ft depth) with a reserve volume totaling 0.86 million gallons (13.33 ft.) and with a total capacity of one million gallons.

7. The effluent is chlorinated by means of a chlorine contact tank, utilizing a 1% chlorine solution with the chlorine feeder pump activated with the spray pump cycle. During the operating season, the spray system is operated on a daily basis and an average of 0.75 to 1.25 inches of depth is removed from the pond daily. This amount provides for a minimum ten-day retention time. The amount of time the system operates is adjusted according to the previous day's accumulation of flow. Fifteen minutes of spray time is approximately equivalent to 1500 gallons of effluent. The irrigation pump and chlorination systems were also destroyed during the recent fire. It is anticipated that they will be replaced by components similar to those which existed previously.
8. The seasonal cycle includes a winter period starting in October, when there is minimal flow into the system. At this time, the pond is lowered to three foot in depth, allowing for an average rainfall of 58.8 inches (estimated fifty year maximum rainfall event).
9. The 2.25 acre spray field is up slope from the pond. The overflow collection trench collects all of the excessive runoff from the irrigation and storm water runoff. The collected water is returned to the pond. A bypass valve in the trench is opened during winter to allow storm water runoff to leave the trench.
10. Annual precipitation at San Jose Family Camp is approximately 38 inches. The annual evaporation rate for this area is reported to be 30 inches per year. The system was sized for a maximum annual rainfall of 58.8 inches. This has been exceeded twice since 1975. The total rainfall in 1983 was 76.07 inches and 62.94 inches in 1995.
11. Water supply is provided by two wells. The water system is inspected and permitted by the County Health Department. Both wells are over 1000 feet from the wastewater pond and sprayfield.
12. The California Department of Health Services has established statewide reclamation criteria in Title 22, California Code of Regulations, Section 60301, et seq. (hereafter Title 22) for the use of reclaimed water, and has developed guidelines for specific uses. These requirements implement the reclamation criteria in Title 22.

WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025
CITY OF SAN JOSE, SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

-3-

13. The Board adopted a Water Quality Control Plan, Fourth Edition, for the Sacramento River Basin and the San Joaquin River Basin (hereafter Basin Plan), which contains water quality objectives for all water of the Basin. These requirements implement the Basin Plan.
14. The beneficial uses of the Tuolumne River via Middle Fork and South Fork Tuolumne Rivers are municipal, industrial, and agricultural supply; recreation; aesthetic enjoyment; navigation; fresh water replenishment; preservation and enhancement of fish, wildlife, and other aquatic resources.
15. Beneficial uses of the underlying groundwater in the camp include domestic, industrial, and agricultural supply.
16. The action to update waste discharge requirements for this facility is exempt from the provisions of the California Environmental Quality Act (CEQA), in accordance with Title 14, California Code of Regulations (CCR), Section 15301.
17. This discharge is exempt from the requirements of Title 27, CCR, Section 20080, et seq. The exemption, pursuant to Section 20090 (b), is based on the following:
 - a. the Board is issuing waste discharge requirements, and
 - b. the discharge complies with the Basin Plan, and
 - c. the wastewater does not need to be managed according to 22 CCR, Division 4.5, Chapter 11 as hazardous waste.
18. The Board has notified the Discharger and interested agencies and persons of its intent to prescribe waste discharge requirements for this discharge and has provided them with an opportunity for a public hearing and an opportunity to submit their written views and recommendations.
19. The Board, in a public meeting, heard and considered all comments pertaining to the discharge.

IT IS HEREBY ORDERED that Order No. 75-109 is rescinded and that San Jose Family Camp, their agents, successors, and assigns, in order to meet the provisions contained in Division 7 of the California Water Code and regulations adopted thereunder, shall comply with the following:

A. Discharge Prohibitions:

1. Discharge of waste to surface waters or surface water drainage courses is prohibited.
2. Bypass or overflow of untreated or partially treated waste is prohibited.

WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025
CITY OF SAN JOSE, SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

-4-

3. Discharge of waste classified as 'hazardous' under Section 2521, Chapter 15 of Title 23 or 'designated', as defined in Section 13173 of California Water Code is prohibited.
4. Excessive irrigation with reclaimed water which results in excessive runoff of reclaimed water, or continued irrigation of reclaimed water during periods of rain is prohibited.
5. The Discharger shall not open the facility for the summer 2000 season until the portions of the waste disposal system destroyed by the fire have been replaced in conformance with this Order.

B. Discharge Specifications:

1. The average dry weather discharge flow shall not exceed 10,550 gallons per day.
2. Objectionable odors originating at this facility shall not be perceivable beyond the limits of the wastewater treatment and disposal areas.
3. As a means of discerning compliance with Discharge Specification No. 2, the dissolved oxygen content in the upper zone (1 foot) of wastewater in ponds shall not be less than 1.0 mg/l.
4. The Discharger's wastewater treatment plant shall be designed, constructed, operated, and maintained to prevent inundation or washout due to floods with a 100-year return frequency.
5. The storage ponds shall not have a pH less than 6.5 or greater than 8.5.
6. Treated effluent used for irrigation shall not exceed the following limits:

<u>Constituent</u>	<u>Units</u>	<u>30-Day Average</u>	<u>30-Day Median</u>	<u>Daily Maximum</u>
BOD ₅	mg/l	40	--	80
Total Coliform Organisms	MPN/100 ml	--	23	230

7. The storage ponds shall be managed to prevent breeding of mosquitoes. In particular,
 - a. An erosion control program should assure that small coves and irregularities are not created around the perimeter of the water surface.

WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025
CITY OF SAN JOSE, SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

-5-

- b. Weeds shall be minimized through control of water depth, harvesting, or herbicides.
 - c. Dead algae, vegetation, and debris shall not accumulate on the water surface.
8. Public contact with wastewater shall be precluded through such means as fences, signs, and other acceptable alternatives.
 9. The storage ponds shall have sufficient capacity to accommodate allowable wastewater flow, designed seasonal precipitation, and ancillary inflow and infiltration during the nonirrigation season. Design seasonal precipitation shall be based on total annual precipitation using a return period of 100 years, distributed monthly in accordance with the historical rainfall patterns.
 10. Freeboard shall never be less than two feet, as measured vertically from the water surface to the lowest point of overflow.
 11. On or about 1 October each year, available pond storage capacity shall at least equal the volume necessary to comply with Discharge Specifications No. 8 and No. 9.

C. Reclamation Specifications:

1. The following setback/buffer zones shall be provided at the reclamation areas:

<u>Setback Definition</u>	<u>Irrigation Setback distances (ft)</u>
Disposal field to public roads	50
Disposal field to property lines	50
Disposal field to on-site irrigation well	100
Disposal field to domestic well	500
Disposal field to any food crop	100
Disposal field to drainage course	100

2. Reclaimed water shall not be used for irrigation of food crops for human consumption nor shall these be used in reclamation impoundments.
3. Reclaimed water used for irrigation shall meet the criteria contained in Title 22, Division 4, CCR (Section 60301 et. Seq.).

WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025
CITY OF SAN JOSE, SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

-6-

4. Public contact with the reclaimed water shall be precluded through such means as fences, signs, and other acceptable alternatives.
5. Areas irrigated with reclaimed water shall be managed to prevent breeding of mosquitoes. More specifically,
 - a. Tailwater must be returned and all applied irrigation water must infiltrate completely within 24-hours.
 - b. Ditches not serving as wildlife habitat should be maintained free of emergent, marginal, and floating vegetation.
 - c. Low-pressure and unpressurized pipelines and ditches accessible to mosquitoes shall not be used to store reclaimed water.
6. Reclaimed water for irrigation shall be managed to minimize erosion, runoff, and movement of aerosols from the disposal area.
7. Direct or windblown spray shall be confined to the designated disposal area and prevented from contacting drinking water facilities.
8. The Discharger may not spray irrigate effluent during periods of precipitation and for at least 24 hours after cessation of precipitation, or when winds exceed 30 mph.
9. Neither the treatment nor the use of reclaimed water shall cause a pollution or nuisance as defined by Section 13350 of the California Water Code (CWC).

D. Sludge Disposal

1. Collected screenings, sludges, and other solids removed from liquid wastes shall be disposed of in a manner that is consistent with both Title 27, Division 2, Subdivision 1 and Title 23, Division 3, Chapter 15 of the California Code of Regulations and approved by the Executive Officer.
2. Any proposed change in sludge use or disposal practice from a previously approved practice shall be reported to the Executive Officer and U.S. Environmental Protection Agency (EPA) Regional Administrator at least 90 days in advance of the change.
3. Use and disposal of sewage sludge shall comply with existing Federal and State laws and regulations, including permitting requirements and technical standards included in 40 CFR 503. If the State Water Resources Control Board and the Regional Water Quality Control Boards are given the authority to implement regulation contained in 40 CFR 503, this Order may be reopened to incorporate appropriate time schedules and technical standards.

The Discharger must comply with the standards and time schedules contained in 40 CFR 503 whether or not they have been incorporated into this Order.

4. The Discharger is encourage to comply with the State Guidance Manual issued by the Department of Health Services titled *Manual of Good Practice for Landspreading of Sewage Sludge*.

E. Groundwater Limitations

1. The discharge, in combination with other sources, shall not cause underlying groundwater to contain waste constituents in concentrations statistically greater than background water quality, except for coliform. For coliform, increases shall not cause the most probable number of total coliform organisms to exceed 2.2/100 ml over any 7-day period.

F. Provisions

1. The Discharger shall comply with the Monitoring and Reporting Program No. 5-00-025, which is part of this Order, and any revisions thereto as ordered by the Executive Officer.
2. The Discharger shall comply with the "Standard Provisions and Reporting Requirements for Waste Discharge Requirements", dated 1 March 1991, which are attached hereto and by reference a part of this Order. This attachment and its individual paragraphs are commonly referenced as "Standard Provision(s)."
3. A contingency plan, including notification of the Board and health agencies and outlining actions to be taken when effluent fails to meet required standards, shall be submitted by **15 March 2000**.
4. For the purposes of influent monitoring, a flow meter shall be installed by **1 May 2000**.
5. By **1 June 2000**, the Discharger shall submit the following:
 - a. A water balance analysis evaluating available pond storage capacity versus Discharge Specifications No. 8 and No. 9.
 - b. A final construction report containing a narrative description of the new or replaced waste disposal system components and as-built diagrams. The report shall also contain the results of testing of the wet well. If the wet well leaks, the report shall describe steps taken to eliminate leakage.
6. In the event of any change in control or ownership of land or waste discharge facilities described herein, the Discharger shall notify the succeeding owner or operator of the


WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025
CITY OF SAN JOSE, SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

-8-

existence of this Order by letter, a copy of which shall be immediately forwarded to this office.

7. At least 90 days prior to termination or expiration of any lease, contract, or agreement involving disposal or reclamation areas or off-site reuse of effluent, used to justify the capacity authorized herein and assure compliance with their Order, the Discharger shall notify the Board in writing of the situation and of what measures have been taken or are being taken to assure full compliance with this Order.
8. The Discharger must comply with all conditions of this Order, including timely submittal of technical and monitoring reports as directed by the Executive Officer. Violations may result in enforcement action, including Regional Board or court orders requiring correction action or imposing civil monetary liability, or in revision or rescission of this Order.
9. A copy of this Order shall be kept at the discharge facility for reference by operating personnel. Key operating personnel shall be familiar with its contents.
10. The Board will review this Order periodically and will revise requirements when necessary.

I, GARY M. CARLTON, Executive Officer, do hereby certify the foregoing is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, Central Valley Region, on 28 January 2000.


GARY M. CARLTON, Executive Officer

AMENDED

JRM: 1/28/00

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
CENTRAL VALLEY REGION

MONITORING AND REPORTING PROGRAM NO. 5-00-025

FOR
CITY OF SAN JOSE
SAN JOSE FAMILY CAMP
WASTEWATER TREATMENT AND DISPOSAL FACILITY
TUOLUMNE COUNTY

This monitoring and reporting program (MRP) incorporates requirements for monitoring of the treatment process, stored effluent, and surface water. This MRP is issued pursuant to Water Code Section 13267. The Discharger shall not implement any changes to this MRP unless and until a revised MRP is issued by the Executive Officer. Specific sample station locations shall be approved by Regional Board staff prior to implementation of sampling activities.

INFLUENT MONITORING

The following shall constitute the influent monitoring program:

<u>Constituent</u>	<u>Units</u>	<u>Type of Sample</u>	<u>Sampling Frequency</u>	<u>Reporting Frequency</u>
Flow	mgd	Cumulative	Continuous	Monthly

EFFLUENT MONITORING

Effluent samples shall be collected downstream from the last connection through which wastes can be admitted to the irrigation field at peak season. Samples collected from the outlet structure of the treatment plant shall be considered to be adequately composited. The following shall constitute the effluent monitoring program:

<u>Constituent</u>	<u>Units</u>	<u>Type of Sample</u>	<u>Sampling and Reporting Frequency</u>
20°C BOD ₅ ¹	mg/l	Grab	Monthly, June - October
Total Coliform	MPN/100 ml	Grab	Monthly, June - October
Total Suspended Solids	mg/l	Grab	Monthly, June - October
Settleable Matter	ml/l	Grab	Monthly, June - October
Electrical Conductivity	mhos/cm	Grab	Monthly, June - October
pH	pH units	Grab	Monthly, June - October
Standard Minerals	mg/l	Grab	Monthly, June - October

¹ 5-days, Biochemical Oxygen Demand at 20°C

POND MONITORING

Monitoring of the ponds shall consist of the following:

<u>Constituents</u>	<u>Units</u>	<u>Type of Sample</u>	<u>Sampling and Reporting Frequency</u>
Dissolved Oxygen	mg/l	Grab	Monthly
Freeboard	feet & inches	Observation	Monthly

STREAM MONITORING

The Discharger shall establish a minimum of two surface water sampling stations on the perennial stream: the first shall be approximately 50 feet upstream of the wet well and the second shall be approximately 50 feet downstream of the wet well. Stream monitoring shall include at least the following:

<u>Constituents</u>	<u>Units</u>	<u>Type of Sample</u>	<u>Sampling and Reporting Frequency</u>
Total Coloform	MPN/100 ml	Grab	Monthly
Fecal Coloform	MPN/100 ml	Grab	Monthly
Electrical Conductivity	µmhos/cm	Grab	Monthly
Total Dissolved Solids	mg/l	Grab	Monthly
pH	pH units	Grab	Monthly

REPORTING

In reporting monitoring data, the Discharger shall arrange the data in tabular form so that the date, sample type (e.g., influent, effluent, etc.), and reported analytical result for each sample are readily discernible. The data shall be summarized in such a manner to clearly illustrate compliance with waste discharge requirements and spatial or temporal trends, as applicable. The results of any monitoring done more frequently than required at the locations specified in the Monitoring and Reporting Program shall be reported to the Regional Board.

A. Monthly Reports

Monthly Monitoring Reports for influent, effluent, pond, and stream monitoring shall be submitted to the Regional Board by the 30th day of the following month.


B. Annual Monitoring Report

The December Monthly Report (due by 30 January of each year) shall also serve as an Annual Monitoring Report. At a minimum, the Annual Monitoring Report shall include the following:

1. The contents of a regular monthly report.
2. If requested by staff, tabular and graphical summaries of all monitoring data obtained during the previous year (including influent, effluent, pond, and stream data).
3. A discussion of compliance and the corrective action taken, as well as any planned or proposed actions needed to bring the discharge into full compliance with the waste discharge requirements.
4. A summary of the land management operation after the conclusion of each season, including a discussion of total water application over the season, the total volume of wastewater applied, and the total nutrient loading from wastewater versus agronomic requirements.
5. A discussion of any data gaps and potential deficiencies/redundancies in the monitoring system or reporting program.

The Discharger shall implement the above monitoring program as of the date of this Order.

Ordered by:


GARY M. CARLTON, Executive Officer

28 January 2000

(Date)

INFORMATION SHEET

WASTE DISCHARGE REQUIREMENTS ORDER NO. 5-00-025

CITY OF SAN JOSE

SAN JOSE FAMILY CAMP

WASTEWATER TREATMENT AND DISPOSAL FACILITY


On 10 June 1999, the City of San Jose, San Jose Family Camp (hereafter Discharger) submitted a Report of Waste Discharge to discharge its treated wastewater to land. The wastewater treatment and disposal facilities are owned and operated by the Discharger. San Jose Family Camp occupies approximately 40.25 acres of a 200-acre parcel deeded to USDA Forest Service. Camp facilities include tent platform camping, a dining hall, a water system, recreational facilities, playgrounds, parking, utility buildings, sanitary facilities and a sewage treatment system. Approximately two thousands campers per year are accommodated, and a part-time seasonal manager and volunteers operate the camp.

The camp is in operation only on a seasonal basis, typically from June through September when a maximum of 300 persons could occupy the camp. Flow volumes were originally estimated not to exceed 10,550 gallons per day (gpd) but by all reports, and the average flow volume has never exceeded or approached that value. Wastewater from the Camp is collected in a six foot diameter by twelve-foot deep wet well and is pumped from this lift station to an oxidation pond. The lift station has contained a dual pump and controller system, high water alarm, and a two thousand-gallon overflow reserve storage tank capacity provided by two concrete septic tanks. The pump and controller system were destroyed by a recent fire, which burned portions of the Camp in August 1999. It is anticipated that they will be replaced by components similar to those which existed previously. The oxidation pond is approximately 20,000 square feet in area and has a total depth of approximately fifteen feet. The oxidation pond has mechanical aeration and has an operating volume of 0.795 million gallons (at 12.75 ft depth) with a reserve volume totaling 0.86 million gallons (13.33 ft.) and a total capacity of one million gallons.

During the operating season, the spray system is operated on a daily basis, and an average of 0.75 to 1.25 inches of depth is removed from the pond daily. This amount provides for a minimum ten-day retention time. The amount of time the system operates is adjusted according to the previous day's accumulation of flow. The effluent is chlorinated by means of a chlorine contact tank, utilizing a 1% chlorine solution, with the chlorine feeder pump activated with the spray pump cycle. The irrigation pump and chlorination systems were also destroyed during the recent fire. It is anticipated that they will be replaced by components similar to those which existed previously. The 2.25 acre spray field is up slope from the pond. The overflow collection trench collects all of the excessive runoff from the irrigation and storm water runoff. The collected water is returned to the pond. A bypass valve in the trench is opened during winter to allow storm water runoff to leave the trench.

These WDRs require that the wastewater system be replaced before the camp opens for the summer 2000 season.

jrm: 1/28/00



Project Location:
 San Jose Family Camp Wastewater
 Treatment and Disposal Facility
 Tuolumne County
 USGS Jawbone Ridge Quad
 (not to scale)