

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

BOARD ORDER NO. 6-00-17
WDID NO. 6B261026001

REVISED WASTE DISCHARGE REQUIREMENTS

FOR

MAMMOTH MOUNTAIN SKI AREA
WASTEWATER TREATMENT PLANT

Mono County

The California Regional Water Quality Control Board, Lahontan Region (Regional Board) finds:

1. Discharger

Mammoth Mountain Ski Area is located approximately five miles (8.0 km) west of the Community of Mammoth Lakes. The designated disposal sites are located on federal lands administered by the U.S. Department of Agriculture, Forest Service. For the purposes of this Regional Board Order (Order), Mammoth Mountain Ski Area and the U.S. Forest Service are referred to as the "Dischargers."

2. Facility

The number of people utilizing the main lodge related facilities averages 4,700 persons per day with a maximum of up to 14,000 skiers at one time. The facilities that contribute to the wastewater flow are the Mammoth Mountain Inn, Mid-Chalet, Main Lodge, Mammoth Mountain Apartments, Mammoth Mountain Chalets, Yodler Haus, and the Yodler Bar. For the purposes of this Order, the Wastewater Treatment Plant will be referred to as the "Facility."

3. Permit History

The Regional Board initially established Waste Discharge Requirements (WDRs) for the Mammoth Mountain Ski Area in 1968 and revised the WDRs under Board Order No. 6-80-20, which was adopted on March 13, 1980. After construction of pond D, the WDRs were revised on January 1, 1984 in Board Order No. 6-84-11.

4. Reason for Action

The Regional Board is revising the WDRs for the Facility as part of a routine program to revise all WDRs. The WDRs are being revised in order to incorporate changes in Regional Board policy /and document upgrades in the treatment system.

In the fifteen years since the last Board Order update, a new emergency pond was constructed, usage has increased, and three ground water monitoring wells were installed. The ground water monitoring wells were installed in 1998 in response to a request from Board staff for a feasibility study to determine compliance of the unlined ponds with the Lahontan Region Basin Plan.

In accordance to the Basin Plan, if degradation of the ground water is detected at any time after the first two years of semi-annual ground water monitoring, WDRs will be evaluated for revision. This revision may require that treatment of the discharge be upgraded to a secondary level within two years. If no degradation is detected, the discharge may be allowed to continue with ongoing sampling of the ground monitoring wells.

5. Facility Location

Mammoth Mountain Ski Area is located approximately five miles (8.0 km) west of the Community of Mammoth Lakes. The treatment and disposal facilities are located in the Long Valley Subunit of the Owens Hydrologic Unit within NW/4, SE/4, Section 30, T3S, R27E, MDB&M.

6. Description of Facility and Discharge

Wastewater treatment and disposal is provided by four existing evaporation/percolation ponds, none of which are lined. A fifth pond has been constructed and designed only for emergency situations. Wastewater flow can alternate between A and B pond. C and D ponds are used for percolation. E pond was constructed for emergency purposes. The Facility collects, treats, and disposes of an average of 0.070 million gallons per day (mgd) of domestic wastewater.

7. Authorized Disposal Sites

The evaporation/percolation ponds are the only authorized disposal sites for wastewater. The authorized disposal site is located on land owned by the Dischargers.

8. Sludge Treatment and Disposal

Dried sludge is periodically removed from the drying ponds. This sludge is then disposed at the Benton Crossing Landfill. Sludge removal is planned only as necessary.

9. Site Geology

The soils underlying the proposed disposal site consist of broken pumice rock to a depth of approximately 50 feet (15.2 m). The disposal site is located in the Dry Creek watershed. Although no permanent ground water is believed to exist at the site, transient ground water does occur during spring runoff periods. The Dischargers have installed a pipe system to divert snowmelt runoff and high ground water around the ponds.

10. Site Hydrogeology

Depth to ground water is estimated to range from 40 - 100 feet. The nearest domestic water wells are located approximately $\frac{3}{4}$ of a mile and uphill from the disposal site.

11. Site Hydrology

All storm water at the Facility is regulated under the State Amended General Industrial Activities Storm Water Permit. Storm water control features have been incorporated into the Storm Water Management Plan for the Facility to divert storm water away from the ponds and Disposal Area.

12. Receiving Waters

The receiving waters are the ground waters of the Upper Owens Hydrologic Area of the Owens Hydrologic Unit (Department of Water Resources Hydrologic Unit No. 603.20).

13. South Lahontan Basin Plan

The Regional Board adopted a Water Quality Control Plan for the South Lahontan Basin (Basin Plan) on March 31, 1995, and this Order implements the Basin Plan as amended.

14. Beneficial Uses

The beneficial uses of the ground waters of the Upper Owens Hydrologic Area of the Owens Hydrologic Unit as set forth and defined in the Basin Plan are:

- a. Municipal and domestic supply;
- b. Agricultural supply;
- c. Industrial service supply; and
- d. Freshwater replenishment.

15. California Environmental Quality Act Compliance

The revised WDRs apply to an existing discharge resulting from an existing Facility and as such are exempt from the provisions of the California Environmental Quality Act (Public Resources Code, Section 21000 et seq.) in accordance with Title 14, Section 15301 of the California Code of Regulations.

16. Notification of Interested Parties

The Regional Board has notified the Dischargers and interested parties of its intent to revise WDRs for the discharge.

17. Consideration of Public Comments

The Regional Board, in a public meeting, heard and considered all comments pertaining to the discharge.

IT IS HEREBY ORDERED that the Dischargers shall comply with the following:

I. DISCHARGE SPECIFICATIONS

A. Effluent/Discharge Limitations

1. The total effluent flow of wastewater during a 24-hour period shall not exceed 0.250 million gallons.
2. All wastewater discharged to the authorized disposal sites shall not contain concentrations of constituents in excess of the following limits:

<u>Parameter</u>	<u>Units</u>	<u>Mean¹</u>	<u>Maximum</u>
Settleable Solids	ml/L	1	2.5
Methylene Blue Active Substances	mg/L	1.0	2.0

3. All wastewater discharged to the authorized disposal site shall have a pH of not less than 6.0 pH units nor more than 9.0 pH units.
4. All wastewater discharged to the authorized disposal sites shall have a dissolved oxygen concentration not less than 1.0 mg/L.

B. Receiving Water Limitations

The discharge of waste shall not cause the presence of the following substances or conditions in ground waters of the Owens Hydrologic Unit:

1. Any perceptible color, odor, taste or foaming;
2. Coliform organisms attributable to human wastes;
3. Toxic substances in concentrations that individually, collectively, or cumulatively cause detrimental physiological responses in human, plants, animals, or aquatic life;

¹ The arithmetic mean of lab results for effluent samples collected in a period of 30 consecutive days.

4. Identifiable chlorinated hydrocarbons, organophosphates, carbamates, and other pesticide and herbicide groups, in summations, in excess of the lowest detectable levels; and
5. Concentrations of chemical constituents in excess of the maximum contaminant levels or secondary maximum contaminant levels based upon drinking water standards specified by the more restrictive of the California Code of Regulations, Title 22, Division 4, Chapter 15, or 40 CFR, Part 141.

C. General Requirements and Prohibitions

1. There shall be no discharge, bypass, or diversion of raw or partially treated sewage, sewage sludge, grease, or oils from the collection, transport, treatment, or disposal facilities to adjacent land areas or surface waters.
2. Surface flow or visible discharge of sewage or sewage effluent from the authorized disposal sites to adjacent land areas or surface waters is prohibited.
3. The vertical distance between the liquid surface elevation and the lowest point of a pond dike or the invert of an overflow structure shall not be less than two (2) feet.
4. The discharge shall not cause a pollution as defined in Section 13050 of the California Water Code, or a threatened pollution.
5. Neither the treatment nor the discharge shall cause a nuisance as defined in Section 13050 of the California Water Code.
6. The discharge of wastewater except to the authorized disposal site is prohibited.

II. PROVISIONS

A. Rescission of WDRs

Board Order No. 6-84-11 hereby rescinded.

B. Operator Certification

The Facility shall be supervised by persons possessing a wastewater treatment plant operator certificate of appropriate grade pursuant to Chapter 3, Subchapter 14, Title 23, California Code of Regulations.

C. Standard Provisions

The Discharger shall comply with the "Standard Provisions for WDRs," dated September 1, 1994, in Attachment "C", which is made a part of this Order.


D. Monitoring and Reporting

1. Pursuant to the California Water Code Section 13267(b), the Discharger shall comply with Monitoring and Reporting Program No. 00-17 as specified by the Executive Officer.
2. The Discharger shall comply with the "General Provisions for Monitoring and Reporting," dated September 1, 1994, which is attached to and made a part of the Monitoring and Reporting Program.


E. Time Schedule Compliance

By **March 9, 2002**, the Discharger shall submit a technical report signed by a Registered Civil Engineer, California Certified Engineering Geologist or a California Registered Geologist documenting the ability of the Facility to meet WDRs. Specifically, the report shall evaluate whether there is, or is not, a potential for degradation or pollution to ground water as described in the California Water Code and State Water Resource Control Board Resolution No. 68-16. Recommendations shall be made regarding the monitoring systems and upgrades to the treatment system.

I, Harold J. Singer, Executive Officer, do hereby certify that the foregoing is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, Lahontan Region, on March 9, 2000.


HAROLD J. SINGER
EXECUTIVE OFFICER

Attachments: A. Location Map
B. Wastewater Facility Layout
C. Standard Provisions for WDRs

[illegible]

QUADRANGLE LOCATION

CONTOURS AND ELEVATIONS IN METERS
ROAD LEGEND

Improved Road.....

Unimproved Road.....

Trail.....

 Interstate Route  U.S. Route  State Route

MAMMOTH MTN., CALIF

PROVISIONAL EDITION 1984

37119--F1--TM--024

TERS


10 METERS
EST 0.1 METER
EST METER
2808
3048

CURACY STANDARDS

DO 80225, OR RESTON, VIRGINIA 22092

1	2	3	1	Koip Peak
			2	June Lake
4		5	3	Crestview
			4	Mt. Ritter
			5	Old Mammoth
6	7	8	6	Cattle Mtn.
			7	Crystal Crag
			8	Blondy Mtn.

ADJOINING 7.5' QUADRANGLE NAMES



Mammoth Mountain Ski Area Sewage Treatment Facility

Scale 1:200

Township 3 South
Range 27 East
Section 30

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD

STANDARD PROVISIONS
FOR WASTE DISCHARGE REQUIREMENTS

ATTACHMENT "C"

1. **Inspection and Entry**

The Discharger shall permit Regional Board staff:

- a. to enter upon premises in which an effluent source is located or in which any required records are kept;
- b. to copy any records relating to the discharge or relating to compliance with the Waste Discharge Requirements;
- c. to inspect monitoring equipment or records; and
- d. to sample any discharge.

2. **Reporting Requirements**

- a. Pursuant to California Water Code 13267(b), the Discharger shall immediately notify the Regional Board by telephone whenever an adverse condition occurred as a result of this discharge; written confirmation shall follow within two weeks. An adverse condition includes, but is not limited to, spills of petroleum products or toxic chemicals, or damage to control facilities that could affect compliance.
- b. Pursuant to California Water Code Section 13260(c), any proposed material change in the character of the waste, manner or method of treatment or disposal, increase of discharge, or location of discharge, shall be reported to the Regional Board at least 120 days in advance of implementation of any such proposal. This shall include, but not limited to, all significant soil disturbances.
- c. The Owners/Discharger of property subject to Waste Discharge Requirements shall be considered to have a continuing responsibility for ensuring compliance with applicable Waste Discharge Requirements in the operations or use of the owned property. Pursuant to California Water Code Section 13260(c), any change in the ownership and/or operation of property subject to the Waste Discharge Requirements shall be reported to the Regional Board. Notification of applicable Waste Discharge Requirements shall be furnished in writing to the new owners and/or operators and a copy of such notification shall be sent to the Regional Board.
- d. If a Discharger becomes aware that any information submitted to the Regional Board is incorrect, the Discharger shall immediately notify the Regional Board, in writing and correct that information.
- e. Reports required by the Waste Discharge Requirements, and other information requested by the Regional Board, must be signed by a duly authorized representative of the Discharger. Under Section 13268 of the California Water Code, any person failing or refusing to furnish technical or monitoring reports, or falsifying any information provided therein, is guilty of a misdemeanor and may be liable civilly in an amount of up to one thousand dollars (\$1,000) for each day of violation.

- f. If the Discharger becomes aware that their Waste Discharge Requirements (or permit) is no longer needed (because the project will not be built or the discharge will cease) the Discharger shall notify the Regional Board in writing and request that their Waste Discharge Requirements (or permit) be rescinded.

3. Right to Revise Waste Discharge Requirements

The Regional Board reserves the privilege of changing all or any portion of the Waste Discharge Requirements upon legal notice to and after opportunity to be heard is given to all concerned parties.

4. Duty to Comply

Failure to comply with the Waste Discharge Requirements may constitute a violation of the California Water Code and is grounds for enforcement action or for permit termination, revocation and reissuance, or modification.

5. Duty to Mitigate

The Discharger shall take all reasonable steps to minimize or prevent any discharge in violation of the Waste Discharge Requirements which has a reasonable likelihood of adversely affecting human health or the environment.

6. Proper Operation and Maintenance

The Discharger shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) that are installed or used by the Discharger to achieve compliance with the Waste Discharge Requirements. Proper operation and maintenance includes adequate laboratory control, where appropriate, and appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities or similar systems that are installed by the Discharger, when necessary to achieve compliance with the conditions of the Waste Discharge Requirements.

7. Waste Discharge Requirement Actions

The Waste Discharge Requirements may be modified, revoked and reissued, or terminated for cause. The filing of a request by the Discharger for waste discharge requirement modification, revocation and reissuance, termination, or a notification of planned changes or anticipated noncompliance, does not stay any of the Waste Discharge Requirements conditions.

8. Property Rights

The Waste Discharge Requirements do not convey any property rights of any sort, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state or local laws or regulations.

9. Enforcement

The California Water Code provides for civil liability and criminal penalties for violations or threatened violations of the Waste Discharge Requirements including imposition of civil liability or referral to the Attorney General.

10. Availability

A copy of the Waste Discharge Requirements shall be kept and maintained by the Discharger and be available at all times to operating personnel.

11. Severability

Provisions of the Waste Discharge Requirements are severable. If any provision of the requirements is found invalid, the remainder of the requirements shall not be affected.

12. Public Access

General public access shall be effectively excluded from disposal/treatment facilities.

13. Transfers

Providing there is no material change in the operation of the facility, this Order may be transferred to a new owner or operator. The owner/operator must request the transfer in writing and receive written approval from the Regional Board's Executive Officer.

14. Definitions

- a. "Surface waters" as used in this Order, include, but are not limited to, live streams, either perennial or ephemeral, which flow in natural or artificial water courses and natural lakes and artificial impoundments of waters. "Surface waters" does not include artificial water courses or impoundments used exclusively for wastewater disposal.
- b. "Ground waters" as used in this Order, include, but are not limited to, all subsurface waters being above atmospheric pressure and the capillary fringe of these waters.

15. Storm Protection

- a. All facilities used for collection, transport, treatment, storage, or disposal of waste shall be adequately protected against overflow, washout, inundation, structural damage or a significant reduction in efficiency resulting from a storm or flood having a recurrence interval of once in 100 years.

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

REVISED MONITORING AND REPORTING PROGRAM NO. 00-17
WDID NO. 6B261026001

FOR

MAMMOTH MOUNTAIN SKI AREA
WASTEWATER TREATMENT PLANT

Mono County

I. MONITORING

A. Flow Monitoring

The Dischargers shall monitor and report the following:

1. The total volume, in million gallons, of wastewater flow to the Facility for each day.
2. The total volume in million gallons, of wastewater flow to the Facility calculated for each month.
3. The maximum instantaneous flow rate, in million gallons per day (mgd) of wastewater to the treatment facility that occurs each day.
4. The average flow rate, in mgd, of wastewater flow to the Facility calculated for each month.
5. The freeboard (distance from the top of the lowest part of the dike to the wastewater surface in a pond) measured each month in each pond when the pond is accessible. If the pond does not contain wastewater, indicate that it is empty. If the ponds are inaccessible, indicate so and provide an explanation why they are inaccessible.

B. Facility Effluent Monitoring

Grab samples of the effluent discharged to the first pond from which percolation can occur, shall be collected and analyzed to determine the magnitude of the following parameters:

<u>Parameter</u>	<u>Units</u>	<u>Frequency</u>
pH	pH units	Weekly ¹
Dissolved Oxygen	mg/L	Weekly ¹
Biochemical Oxygen Demand	mg/L	Monthly
Methylene Blue Active Substances	mg/L	Monthly
Settleable Solids	ml/L	Monthly
Total Dissolved Solids	mg/L	Semiannually
Kjeldahl Nitrogen	mg/L as N	Monthly
Nitrate Nitrogen	mg/L as N	Monthly
Ammonia Nitrogen	mg/L as N	Monthly
Chloride	mg/L	Semiannually
Sodium	mg/L	Semiannually
Sulfate	mg/L	Semiannually
Total Hardness as CaCO ₃	mg/L	Semiannually
Boron	mg/L	Semiannually
Fluoride	mg/L	Semiannually
Chemical Oxygen Demand	mg/L	Annually in summer
Oil & Grease	mg/L	Annually in summer
Methyl Tertiary Butyl Ether	ug/L	Annually in summer
Purgeable Organics ^{2,3}	ug/L	Monthly in summer
Base/Neutral/Acid ^{2,3} Extractables	ug/L	Monthly in summer

C. Sludge Disposal

1. The Dischargers shall submit a Sludge Management Plan (Plan) 90 days prior to any planned cleaning operation of the sludge drying bed. The Plan shall outline actions necessary for the Discharger to be in compliance with all local, state and federal laws and regulations. Copies of reports submitted to other agencies regarding sludge disposal operations shall be included in the Plan.
2. The Dischargers shall submit the date and quantity of any sludge landfilled or removed off site, location of use, recipient (including name and address) and sludge disposal method for all sludge removed off site.
3. The Dischargers shall submit cumulative total quantity of sludge currently stockpiled on site including the quantity of sludge added to the stockpile during this monitoring period. For sewage sludge removed from the ponds, stockpiled on site, or discharged offsite during the previous month, a representative sample shall be collected and analyzed for the following constituents:

¹ Monitoring for this parameter, shall be monthly between the months of October to May.

² Analyze for all appropriate substances included on the US EPA list of Priority Pollutants (attached) and all other toxic substances known to be discharged to the Discharger's sewer system. The list of Priority Pollutants is found in 40 CFR 131.36 (b).

³ Purgeable Organics and Base/Neutral/Acid Extractables, and Heavy Metals are to be sampled and analyzed at the specified frequency for the first year and semiannually thereafter.

- a. total kjeldahl nitrogen as N;
 - b. ammonia nitrogen as N;
 - c. nitrate nitrogen as N;
 - d. total phosphate as P; and
 - e. parameters listed in Section 66261.24, Chapter 30, Division 4, Title 22, California Code of Regulations or 40 CFR 261.31.
4. The Discharger shall make a determination whether the analyses indicate that the sludge shall be considered a hazardous material.
 5. At least 90 days prior to sample collection and analysis, a sludge sampling protocol shall be submitted for approval.

II. REPORTING

A. General Provisions

The Discharger shall comply with the "General Provisions for Monitoring and Reporting dated September 1, 1994, which is attached to and made a part of this Monitoring and Reporting Program.

B. Submittal Periods


Quarterly Monitoring Reports containing the above-required information shall be submitted to the Regional Board by the 15th day following the end of each quarter.

By January 30, 2001 and each year thereafter, the Discharger shall submit an annual report summarizing the previous year's monitoring data using graphs and tables.

C. Time Schedule

In accordance with the attached General Provisions for Monitoring and Reporting, the Discharger shall submit a Sampling and Analysis Plan (SAP) for the Facility by June 15, 2000. The SAP shall specify sample collection, preservation and shipment protocol, Field Procedures, laboratory Quality Assurance/Quality Control and data quality.

Ordered by:


HAROLD J. SINGER
EXECUTIVE OFFICER

Dated: March 9, 2000

Attachments: A. General Provisions for Monitoring and Reporting
B. Priority Pollutants

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

GENERAL PROVISIONS
FOR MONITORING AND REPORTING

1. SAMPLING AND ANALYSIS

- a. All analyses shall be performed in accordance with the current edition(s) of the following documents:
 - i. Standard Methods for the Examination of Water and Wastewater
 - ii. Methods for Chemical Analysis of Water and Wastes, EPA
- b. All analyses shall be performed in a laboratory certified to perform such analyses by the California State Department of Health Services or a laboratory approved by the Regional Board. Specific methods of analysis must be identified on each laboratory report.
- c. Any modifications to the above methods to eliminate known interferences shall be reported with the sample results. The method used shall also be reported. If methods other than USEPA approved methods or Standard Methods are used, the exact methodology must be submitted for review and must be approved by the Regional Board prior to use.
- d. The Discharger shall establish chain-of-custody procedures to ensure that specific individuals are responsible for sample integrity from commencement of sample collection through delivery to an approved laboratory. Sample collection, storage and analysis shall be conducted in accordance with an approved Sampling and Analysis Plan (SAP). The most recent version of the approved SAP shall be kept at the facility.
- e. The Discharger shall calibrate and perform maintenance procedures on all monitoring instruments and equipment to ensure accuracy of measurements, or shall ensure that both activities will be conducted. The calibration of any wastewater flow measuring device shall be recorded and maintained in the permanent log book described in 2.b, below.
- f. A grab sample is defined as an individual sample collected in fewer than 15 minutes.
- g. A composite sample is defined as a combination of no fewer than eight individual samples obtained over the specified sampling period at equal intervals. The volume of each individual sample shall be proportional to the discharge flow rate at the time of sampling. The sampling period shall equal the discharge period, or 24 hours, whichever period is shorter.

2. OPERATIONAL REQUIREMENTS

a. Sample Results

Pursuant to California Water Code Section 13267(b), the Discharger shall maintain all sampling and analytical results including: strip charts; date, exact place, and time of sampling; date analyses were performed; sample collector's name; analyst's name; analytical techniques used; and results of all analyses. Such records shall be obtained for a minimum of three years. This period of retention shall be extended during the course of any unresolved litigation regarding this discharge, or when requested by the Regional Board.

b. Operational Log

Pursuant to California Water Code Section 13267(b), an operation and maintenance log shall be maintained at the facility. All monitoring and reporting data shall be recorded in a permanent log book.

3. REPORTING

- a. For every item where the requirements are not met, the Discharger shall submit a statement of the actions undertaken or proposed which will bring the discharge into full compliance with requirements at the earliest time and submit a timetable for correction.
- b. Pursuant to California Water Code Section 13267(b), all sampling shall be made available to the Regional Board upon request. Results shall be retained for a minimum of three years. This period of retention shall be extended during the course of any unresolved litigation regarding this discharge, or when requested by the Regional Board.
- c. The Discharger shall provide a brief summary of any operational problems and maintenance activities to the Regional Board with each monitoring report. Any modifications or additions to, or any major maintenance conducted on, or any major problems occurring to the wastewater conveyance system, treatment facilities, or disposal facilities shall be included in this summary.
- d. Monitoring reports shall be signed by:
 - i. In the case of a corporation, by a principal executive officer at least of the level of vice-president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which the discharge originates;
 - ii. In the case of a partnership, by a general partner;

- iii. In the case of a sole proprietorship, by the proprietor;
 - iv. In the case of a municipal, state or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
- e. Monitoring reports are to include the following:
- i. Name and telephone number of individual who can answer questions about the report.
 - ii. The Monitoring and Reporting Program Number.
 - iii. WDID Number.
- f. Modifications

This Monitoring and Reporting Program may be modified at the discretion of the Regional Board Executive Officer.

4. NONCOMPLIANCE

Under Section 13268 of the Water Code, any person failing or refusing to furnish technical or monitoring reports or falsifying any information provided therein, is guilty of a misdemeanor and may be liable civilly in an amount of up to one thousand dollars (\$1,000) for each day of violation under Section 13268 of the Water Code.

126 Priority Pollutants

- A. Chlorinated Benzenes
 - Chlorobenzene
 - 1,2-dichlorobenzene
 - 1,3-dichlorobenzene
 - 1,4-dichlorobenzene
 - 1,2,4-trichlorobenzene
 - Hexachlorobenzene
- B. Chlorinated Ethanes
 - Chloroethane
 - 1,1-dichloroethane
 - 1,2-dichloroethane
 - 1,1,1-trichloroethane
 - 1,1,2-trichloroethane
 - 1,1,2,2-tetrachloroethane
 - Hexachloroethane
- C. Chlorinated Phenols
 - 2-chlorophenol
 - 2,4-dichlorophenol
 - 2,4,6-trichlorophenol
 - Parametachlorocresol (4-chloro-3-methyl phenol)
- D. Other Chlorinated Organics
 - Chloroform (trichloromethane)
 - Carbon tetrachloride (tetrachloromethane)
 - Bis(2-chloroethoxy)methane
 - Bis(2-chloroethyl)ether
 - 2-chloroethyl vinyl ether (mixed)
 - 2-chloronaphthalene
 - 3,3-dichlorobenzidine
 - 1,1-dichloroethylene
 - 1,2-trans-dichloroethylene
 - 1,2-dichloropropane
 - 1,2-dichloropropylene (1,3-dichloropropene)
 - Tetrachloroethylene
 - Trichloroethylene
 - Vinyl chloride (chloroethylene)
 - Hexachlorobutadiene
 - Hexachlorocyclopentadiene
 - 2,3,7,8-tetrachloro-dibenzo-p-dioxin (TCDD)
- E. Haloethers
 - 4-chlorophenyl phenyl ether
 - 2-bromophenyl phenyl ether
 - Bis(2-chloroisopropyl) ether
- F. Halomethanes
 - Methylene chloride (dichloromethane)
 - Methyl chloride (chloromethane)

Methyl Bromide (bromomethane)
Bromoform (tribromomethane)
Dichlorobromomethane
Chlorodibromomethane

G. Nitrosamines

N-nitrosodimethylamine
N-nitrosodiphenylamine
N-nitrosodi-n-propylamine

H. Phenols (other than chlorinated)

2-nitrophenol
4-nitrophenol
2,4-dinitrophenol
4,6-dinitro-o-cresol (4,6-dinitro-2-methylphenol)
Pentachlorophenol
Phenol
2,4-dimethylphenol

I. Phthalate Esters

Bis(2-ethylhexyl)phthalate
Butyl benzyl phthalate
Di-N-butyl phthalate
Di-n-octyl phthalate
Diethyl phthalate
Dimethyl phthalate

J. Polynuclear Aromatic Hydrocarbons (PAHs)

Acenaphthene
1,2-benzanthracene (benzo(a) anthracene)
Benzo(a)pyrene (3,4-benzo-pyrene)
3,4-benzofluoranthene (benzo(b) fluoranthene)
11,12-benzofluoranthene (benzo(k) fluoranthene)
Chrysene
Acenaphthalene
Anthracene
1,12-benzoperylene (benzo(ghi) perylene)
Fluorene
Fluoranthene
Phenanthrene
1,2,5,6-bibenzanthracene (dibenzo(ah) anthracene)
Indeno (1,2,3-cd) pyrene (2,3-o-phenylene pyrene)
Pyrene

K. Pesticides and Metabolites

Aldrin
Dieldrin
Chlordane (technical mixture and metabolites)
Alpha-endosulfan
Beta-endosulfan
Endosulfan sulfate
Endrin
Endrin aldehyde
Heptachlor
Heptachlor epoxide (BHC-hexachlorocyclohexane)

Alpha-BHC
Beta-BHC
Gamma-BHC (Lindane)
Delta-BHC
Toxaphene

L. DDT and Metabolites

4,4-DDT
4,4-DDE (p,p-DDX)
4,4-DDD (p,p-TDE)

M. Polychlorinated Biphenyls (PCBs)

PCB-1242 (Arochlor 1242)
PCB-1254 (Arochlor 1254)
PCB-1221 (Arochlor 1221)
PCB-1232 (Arochlor 1232)
PCB-1248 (Arochlor 1248)
PCB-1260 (Arochlor 1260)
PCB-1016 (Arochlor 1016)

N. Other Organics

Acrolein
Acrylonitrile
Benzene
Benzidine
2,4-dinitrotoluene
2,6-dinitrotoluene
1,2-diphenylhydrazine
Ethylbenzene
Isophorone
Naphthalene
Nitrobenzene
Toluene

O. Inorganics

Antimony
Arsenic
Asbestos
Beryllium
Cadmium
Chromium
Copper
Cyanide, total
Lead
Mercury
Nickel
Selenium
Silver
Thallium
Zinc

