

1742
210

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

BOARD ORDER NO. 6-94-57
WDID NO. 6B360106001

UPDATED WASTE DISCHARGE REQUIREMENTS

FOR

CRESTLINE SANITATION DISTRICT

San Bernardino County_____

The California Regional Water Quality Control Board, Lahontan Region (Regional Board) finds:

1. Discharger

The Crestline Sanitation District (District), by submittal of the *Master Plan Update/Environmental Initial Study* (January/February 1993), hereby incorporated by reference, submitted a complete report of waste discharge for District operations on March 3, 1993. For the purposes of this Order, Crestline Sanitation District is referred to as the "Discharger."

2. Facility

The Huston Creek, Seeley Creek, and Cleghorn wastewater treatment plants, the District-owned reclamation site, and the District-owned emergency disposal site are the facilities which the Discharger controls, and are the facilities from which the discharge occurs. For the purposes of this Order, the above-mentioned treatment and disposal areas are collectively referred to as the "Facility". The Facility discharges domestic sewage, septage, and sludge.

Under normal circumstances, the majority of the District's wastewater is used for pasture irrigation at a privately-owned facility, the Rancho Las Flores (formerly Summit Valley Ranch). Rancho Las Flores has agreed to accept effluent from the Discharger, and is regulated under separate reclamation requirements prescribed in Board Order No. 6-85-27 (adopted March 14, 1985). For the purposes of this Order, the three sites where wastewater may be discharged will be distinguished as "Rancho Las Flores", the (District-owned) "reclamation site" and the (District-owned) "emergency disposal site". Under emergency conditions, flow may be diverted from Rancho Las Flores to the emergency disposal site.

3. History of Previous Regulation by the Regional Board

The Regional Board previously established waste discharge requirements for the Crestline Sanitation District under Board Order No. 6-85-25, which was adopted on March 15, 1985, Board Order No. 6-80-22, which was adopted on March 13, 1980, and Board Order No. 6-77-67, which was adopted on June 30, 1977. The Discharger has previously violated waste discharge requirements, resulting in the following enforcement actions.

Administrative Civil Liability Order No. 6-93-82 was adopted by the Regional Board on August 13, 1993, as a result of an unauthorized discharge of disinfected secondary-treated sewage to the West Fork of the Mojave River. More than 11 million gallons were discharged over a 9-day period from an undetected break in the Discharger's outfall line on the Rancho Las Flores. The Discharger completed an alarm installation mitigation project in December of 1993 in lieu of paying an administrative civil liability in the amount \$13,500.

Administrative Civil Liability Order No. 6-89-53 was adopted by the Regional Board on April 14, 1989, as a result of an unauthorized discharge of disinfected secondary-treated sewage to the West Fork of the Mojave River from the authorized disposal site. The Regional Board assessed and collected \$2000 in administrative civil liabilities from the Discharger for the unauthorized discharge.

The Discharger was previously subject to Cease and Desist Order No. 6-78-23, which was adopted by the Regional Board on April 13, 1978 and later amended by the State Water Resources Control Board (SWRCB) through their Order No. WQ 78-12, which was adopted on June 15, 1978. The Cease and Desist Order was issued because of excessive infiltration and inflow in the collection system which resulted in violations of waste discharge requirements and discharge prohibitions. Since the time of adoption of Cease and Desist Order No. 6-78-23, the Discharger has complied with requirements by constructing improved sewage collection, treatment, and disposal systems as described in this Order. The Regional Board rescinded the Cease and Desist Order on February 9, 1989 (Board Order No. 6-89-36). In 1994, the Discharger applied to the SWRCB for a \$7.5 million State Revolving Fund Loan to implement an Inflow and Infiltration Reduction Program, and a \$3.0 million Revolving Fund Loan to implement an Effluent Emergency Storage Project at the Huston and Seeley Creek treatment plants. These loan proposals involve repairing and replacing aging and/or faulty pipe, joints, and laterals, and providing emergency storage capacity to prevent unauthorized discharges, respectively.

4. Reason for Action

The Regional Board is updating waste discharge requirements as part of an ongoing program to periodically review and update waste discharge requirements to reflect current Regional Board policies. The purpose of this Order is to update waste discharge specifications and Facility information.

5. Facility Locations

The Facility is located in the San Bernardino Mountains of San Bernardino County. The Huston Creek treatment plant serves the Lake Gregory, San Moritz, and upper Crestline areas and (together with the District headquarters) is located in the community of Crestline, at 24516 Lake Drive, APN 0337-101-08, within Section 14, T2N, R4W, SBB&M. The Seeley Creek treatment plant serves the Valley of Enchantment area and is located along State Highway 138, one mile north of Camp Seeley, APN 0343-031-03,

within portions of Sections 9 and 16, T2N, R4W, SBB&M. (The Seeley Creek treatment plant is located on federal lands administered by the U.S. Department of Agriculture/Forest Service, San Bernardino National Forest, and is owned and operated by the Discharger under a Special Use Permit.) The Cleghorn facilities serve the Silverwood Lake State Recreational Area and are located on the west side of State Highway 138 near Silverwood Lake, at Cleghorn Road, APN 0341-111-19, within Section 1, T2N, R5W, SBB&M. The reclamation site, approximately six acres of land at the sewage outfall which are regularly irrigated with wastewater, is accessible from State Highway 173, APN 357-231-32, within Section 33, T3N, R4W, SBB&M. Another twelve acres of emergency disposal fields, with approximately one acre of sand percolation beds, are accessible from State Highway 173, APN 357-211-30, with portions in Sections 28 and 29, T3N, R4W, SBB&M. These latter two parcels are located near Rancho Las Flores in Summit Valley. The above-mentioned locations are shown on Attachment "A", which is made part of this Order.

6. Other Facilities

The effluent from the Huston, Seeley Creek, and Cleghorn plants is reclaimed at the 500-acre Rancho Las Flores, located approximately 1500 feet north of Silverwood Lake, and accessible via State Highway 173, APN 0357-231-32, within portions of Section 28, 29, and 33, T3N, R4W, SBB&M. The Discharger also disposes of treated effluent from another area facility, the Pilot Rock treatment plant, which is located six miles north of Crestline on State Highway 138, within Section 10, T2N, R4W, SBB&M. The above-mentioned locations are shown on Attachment "A". The Cleghorn collection system, and the small Pilot Rock treatment plant, are owned and maintained by the California Department of Parks and Recreation, and the California Department of Forestry, respectively, and are regulated under separate waste discharge requirements.

7. Description of Facility and Discharge

The Crestline Sanitation District was formed in 1946 to provide sewer service to the Lake Gregory area and has since grown to serve other areas. The Huston Creek treatment plant is the largest District facility, and provides service to 75% of the sewered area within District boundaries. The remaining 25% of the sewered area within District boundaries is served by the Seeley Creek treatment plant. The Cleghorn treatment plant is owned and operated by the Discharger, but serves areas outside of District boundaries. The combined discharge, including treated effluent from the Pilot Rock treatment plant, consists of sewage collected primarily from residential, recreational, and resort facilities which is treated to secondary level, disinfected, and disposed (reclaimed).

8. Sludge Treatment and Disposal

Primary and secondary sludge from the Seeley Creek, Cleghorn, and Pilot Rock treatment plants is currently hauled by the Discharger to a sludge dewatering facility at the Huston Creek plant, where it is mixed with Huston Creek plant sludge in an aerobic sludge thickener tank and, if necessary, injected with a 50% solution of hydrogen

peroxide to rapidly oxidize the waste and control odors. Current plans are to replace the hydrogen peroxide system with a potassium permanganate system. The Discharger also accepts septage from private septic tank pumper trucks at the Huston Creek plant, and receives approximately 0.16 million gallons of septage per year, primarily in the summer months. Each month, an average of 18 pumper trucks discharge their septage load to a manhole located just upstream of the Huston Creek plant where the septage receives secondary treatment. The combined sludge is dewatered to approximately 30 to 35 percent solids content using a belt press filter and transported by the Discharger to a private composting facility in San Timoteo Canyon owned by Mr. Larry Curti, L. Curti Truck and Equipment Company, and operated under requirements issued by the Santa Ana Regional Water Quality Control Board. The Discharger is currently exploring other permanent solutions for final disposal of sludge, and may utilize alternative sludge treatment and disposal methods and/or areas pending further study.

9. Disposal Area

The Discharger collects, treats and disposes of domestic sewage and septage. Two pump stations and nearly 73 miles of 6 to 8-inch-diameter sewer mains constitute the collection systems. Schematic flow diagrams for the treatment plants operated by the Discharger are shown in Attachment "B" of this Order. The design capacities, and treatment processes for the treatment plants are as follows:

<u>Facility</u>	<u>Design Capacity (Average/Peak)</u>	<u>Treatment Processes</u>
Huston Creek	0.7 mgd / 2.5 mgd	Primary Clarification Fixed-Film Secondary Chlorination
Seeley Creek	0.5 mgd / 1.0 mgd	Primary Clarification Fixed-Film Secondary Chlorination
Cleghorn	0.2 mgd / 0.4 mgd	Extended-Aeration Activated Sludge Secondary Clarification Chlorination
Pilot Rock	0.010 mgd (peak)	Activated Sludge (Package) Chlorination
District Outfall Pipeline	5.0 mgd / 7.5 mgd	Conveyance

Flows to the Discharger's treatment plants vary seasonally. Wet-weather flows typically occur in February, March, and April, and may more than double dry-weather flows due to the influence of infiltration of the collection system by snowmelt and runoff. In addition, District-wide high flows may occur in July, August, and September due to full use of summer camping areas and increased occupancy by absentee homeowners. Wet-day and dry-day flows (based on March and September 1993 monthly averages) are tabulated below for each plant.

<u>Facility</u>	<u>Current Flow (Dry/Wet)</u>
Huston Creek	0.40 mgd / 0.73 mgd
Seeley Creek	0.15 mgd / 0.28 mgd
Cleghorn	0.017 mgd / 0.024 mgd
Pilot Rock	0.009 mgd / 0.010 mgd

The disinfected secondary effluent from the treatment plants is discharged to a common 11-mile-long, 12-inch to 24-inch diameter, outfall pipeline which conveys the wastewater out of the Silverwood Lake watershed to the reclamation site and Rancho Las Flores, located below Silverwood Lake and adjacent to the West Fork of the Mojave River.

10. Authorized Disposal Sites

The Discharger's six-acre reclamation site and Rancho Las Flores are the authorized disposal sites for wastewater. Under emergency conditions, the Discharger is authorized to utilize the 12-acre emergency disposal site containing the sand percolation beds. In addition, the Discharger is authorized to use treated and disinfected wastewater for on-site landscape irrigation of approximately one acre of land at the Huston Creek plant and approximately one acre of land at the Seeley Creek plant. The Curti composting facility in San Timoteo Canyon is currently the only authorized disposal site for sludge. The authorized disposal sites are located on land owned and/or administered as follows: Rancho Las Flores is owned by John Plunkett; the reclamation site and the emergency disposal site are located on land owned by the Crestline Sanitation District; the sludge disposal site is located on private lands controlled by Larry Curti. The Discharger currently maintains an unlined storage pond at the Huston Creek plant, and another unlined pond approximately 1500 feet downgradient from the Seeley Creek plant. These ponds are not authorized disposal sites, and any discharge to these ponds constitutes a violation of waste discharge requirements and applicable waste discharge prohibitions.

11. Reclamation Regulations

The State Department of Health Services has established statewide reclamation criteria for the use of reclaimed water for flood irrigation of agricultural pasture land vegetated with fodder, fiber or seed crops. All effluent made available for reclamation is to comply with standard Department of Health Services Reclamation Requirements as specified in Chapter 3, Division 4, Title 22, California Code of Regulations.

In accordance with Section 13523 of the California Water Code, the Regional Board consulted with and received the recommendations of the State Department of Health Services concerning reclamation requirements which are incorporated within this Order.

12. Site Geology

The Discharger has facilities located within the Crestline, Lake Gregory, and Silverwood Lake areas of the San Bernardino Mountains. The major portion of this mountain range is a block of basement rocks of the Mojave Desert region which have been elevated by the San Andreas Fault Zone and partially overlain by late Cenozoic valley deposits and basalt.

The area is prone to seismic activity and severe groundshaking; the most significant known fault within the immediate geographic area is the San Andreas Fault, located through Cajon Pass east of Crestline, and southeast along the base of the San Bernardino Mountains. The soils in the mountainous areas of the District are rocky and granitic, while soils in the reclamation area are alluvium and consist primarily of sands and gravels.

13. Site Hydrology

The Discharger has facilities located within the Crestline, Lake Gregory and Silverwood Lake areas. Treatment plants are located near Huston Creek, Seeley Creek, and the West Fork of the Mojave River above Silverwood Lake (Cleghorn), respectively. Average annual precipitation rates range from 40 inches at the higher elevations (Crestline) to 20 inches at the lower elevations (Silverwood Lake/Rancho Las Flores). The Discharger's greatest problems occur from inflow and infiltration of the collection systems, which has resulted in combined flows in excess 4 mgd at the reclamation outfall, well above treatment plant capacities. Spills of raw and/or treated sewage have occurred to Lake Gregory and the West Fork of the Mojave River below Silverwood Lake, near the reclamation site. The Discharger currently performs monthly surface water quality monitoring of Huston Creek, Seeley Creek, and Dart Creek for methylene blue active substances, fecal streptococci, fecal coliform, and total coliform, and carries out semi-annual municipal supply water monitoring for total dissolved solids, chloride, sodium, and sulfate (as required by the Regional Board). Surface water resources, particularly at the higher elevations, are considered to be relatively pristine, and of high quality. Lake Gregory reservoir, near Crestline, is drained by Huston Creek to the East Fork of the West Fork of the Mojave River; the Seeley Creek watershed also drains to the East Fork

of the West Fork of the Mojave River. Both the East Fork of the West Fork of the Mojave River, and the (upper) West Fork of the Mojave River enter Silverwood Lake. The (lower) West Fork of the Mojave River flows to the northeast from the dam at Silverwood Lake.

14. Site Hydrogeology

Subsurface hydrology varies widely within the District's sphere of influence. Nonwater-bearing rock and water-bearing sediments are found at the higher elevations. Lake deposits and evaporite in the reclamation areas have ground water levels ranging from approximately 3 to 25 feet below ground surface. Ground water quality is excellent for all beneficial uses, with total dissolved solids concentrations in the range of 200-300 mg/l.

15. Receiving Waters

The receiving waters are the ground waters of the South Lahontan Hydrologic Basin, Mojave Hydrologic Unit, Upper Mojave Hydrologic Area (Department of Water Resources Hydrologic Unit No. 628.20).

16. South Lahontan Basin Plan

The Regional Board adopted a Water Quality Control Plan for the South Lahontan Basin (Basin Plan) on May 8, 1975 and this Order implements the Basin Plan as amended.

17. Beneficial Uses

The beneficial uses of the ground waters of the South Lahontan Hydrologic Basin, Mojave Hydrologic Unit, Upper Mojave Hydrologic Area as set forth and defined in the Basin Plan are:

- a. municipal and domestic supply
- b. agricultural supply
- c. industrial service supply
- d. freshwater replenishment

18. Constituents of Concern and Monitoring Parameters

The Discharger has a history of past violations of effluent limitations for total dissolved solids, chloride, sulfate, and sodium. The Discharger's treatment processes are unable to effectively remove these constituents, which are contained in supply waters. The effluent limitations specified in this Order are revised, and do not include effluent limitation specifications for the above-mentioned constituents. However, receiving water limitations for ground water require that the discharge shall not result in ground water having concentrations of these chemicals in violation of drinking water standards. The Discharger will continue to monitor and report the concentration of the above-named

constituents in the supply water, the effluent discharged to the Rancho Las Flores area, and the ground water in the vicinity of the reclamation site. In addition to the above-mentioned violations, the Discharger has also violated the effluent limitation for methylene blue active substances. The limitation for methylene blue active substances will remain in effect and the Discharger may be liable for violations of this limitation.

19. California Environmental Quality Act Compliance

The Facilities which these waste discharge requirements regulate are existing facilities which the Discharger is currently operating and are therefore exempt from the provisions of the California Environmental Quality Act (Public Resources Code, § 21000, et seq.).

20. Notification of Interested Parties

The Regional Board has notified the Discharger and interested parties of its intent to update waste discharge requirements for the discharge.

21. Consideration of Public Comments

The Regional Board, in a public meeting, heard and considered all comments pertaining to the discharge.

IT IS HEREBY ORDERED that the Discharger shall comply with the following:

I. DISCHARGE SPECIFICATIONS

A. Effluent/Discharge Limitations

1. The total effluent flow of wastewater, in million gallons, during a 24-hour period shall not exceed average design capacity for any treatment Facility as specified in Finding No. 9 of this Order.
2. The maximum (peak) instantaneous flowrate of wastewater, in million gallons per day, shall not exceed peak design capacity for any treatment or disposal facility as specified in Finding No. 9 of this Order.
3. All wastewater made available for percolation at the authorized disposal sites shall not contain pollutant concentrations in excess of the following limits:

<u>Parameter</u>	<u>Units</u>	<u>Mean</u> ¹	<u>Maximum</u>
• BOD ²	mg/l	30	45
• MBAS ³	mg/l	1.0	2.0

- 4. All wastewater made available for percolation at the authorized disposal site shall have a pH of not less than 6 pH units nor more than 9 pH units.
- 5. All wastewater made available for percolation at the authorized disposal site shall have a dissolved oxygen concentration not less than 1.0 mg/l.
- 6. Reclaimed water used for landscape irrigation shall be at all times an adequately disinfected, oxidized wastewater. The wastewater shall be considered adequately disinfected if the median number of coliform organisms in the effluent does not exceed 23 per 100 milliliters, as determined from the bacteriological results of the last 7 days for which analyses have been completed, and the number of coliform organisms does not exceed 240 per 100 milliliters in any two consecutive samples.

If reclaimed water is used for the irrigation of pasture to which milking cows or goats have access, the wastewater shall be at all times an adequately disinfected, oxidized wastewater. The wastewater shall be considered adequately disinfected if at some location in the treatment process the median number of coliform organisms does not exceed 23 per 100 milliliters, as determined from the bacteriological results of the last 7 days for which analyses have been completed

B. Receiving Water Limitations

The discharge of waste shall not cause the presence of the following substances or conditions in ground waters of the Mojave Hydrologic Unit, Upper Mojave Hydrologic Area:

1. Any perceptible color, odor, taste or foaming.
2. Coliform organisms attributable to human wastes.
3. Toxic substances in concentrations that individually, collectively, or cumulatively cause detrimental physiological responses in human, plants, animals, or aquatic life.

¹ The arithmetic mean of lab results for effluent samples collected in a period of 30 consecutive days.

² Biochemical Oxygen Demand (5 day, 20°C) of an unfiltered sample.

³ Methylene Blue Active Substances

4. Identifiable chlorinated hydrocarbons, organophosphates, carbamates, and other pesticide and herbicide groups, in summations, in excess of the lowest detectable levels.
5. Concentrations of chemical constituents in excess of the maximum contaminant levels or secondary maximum contaminant levels based upon drinking water standards specified by the more restrictive of the California Code of Regulations, Title 22, Division 4, Chapter 15, or 40 CFR, Part 141.

C. Reclamation Requirements

1. All effluent made available for reclamation shall comply with standard Department of Health Services Reclamation Requirements as specified in Chapter 3, Division 4, Title 22 of the California Code of Regulations.
2. Reclaimed water used for spray irrigation of fodder, fiber and seed crops shall contain not more than 0.5 ml/l per hour of settleable solids.
3. The irrigation sites shall be graded to prevent persistent ponding of wastewater which is capable of promoting the breeding of mosquitoes.
4. The irrigation sites shall be properly fenced and posted to restrict public access and warn of the presence of sewage.

D. General Requirements and Prohibitions

1. There shall be no discharge, bypass, or diversion of raw or partially treated sewage, sewage sludge, grease, or oils from the collection, transport, treatment, or disposal facilities to adjacent land areas or surface waters.
2. Surface flow or visible discharge of sewage or sewage effluent at, or from, the authorized disposal sites to adjacent land areas or surface waters is prohibited.
3. The vertical distance between the liquid surface elevation and the lowest point of a pond dike or the invert of an overflow structure shall not be less than two (2) feet.
4. The discharge shall not cause a pollution as defined in Section 13050 of the California Water Code, or a threatened pollution.
5. Neither the treatment nor the discharge shall cause a nuisance as defined in Section 13050 of the California Water Code.

6. The discharge of wastewater except to the authorized disposal site is prohibited.
7. The integrity of any pond liners, if present, shall be maintained throughout the life of the ponds and shall not be diminished as the result of any maintenance or cleaning operation.

II. PROVISIONS

A. Rescission of Waste Discharge Requirements

Board Order No. 6-85-25 is hereby rescinded.

B. Standard Provisions

The Discharger shall comply with the "Standard Provisions for Waste Discharge Requirements," dated July 1, 1993, in Attachment "C", which is made part of this Order.

C. Monitoring and Reporting

1. Pursuant to Section 13267(b) of the California Water Code, the Discharger shall comply with the Monitoring and Reporting Program No. 94-57 as specified by the Executive Officer.
2. The Discharger shall comply with the "General Provisions for Monitoring and Reporting," dated July 1, 1993, which is attached to and made part of the Monitoring and Reporting Program.

D. Time Schedule Compliance


The Discharger shall comply with time schedules contained in the Monitoring and Reporting Program:

1. The Discharger shall submit a Sludge Management Plan by not later than January 1, 1995.
2. The Discharger shall fully implement a revised ground water monitoring system plan, as described in the Monitoring and Reporting Program, by not later than January 1, 1995.

E. Operator Certification

The Discharger's wastewater treatment plant shall be supervised by persons possessing a wastewater treatment plant operator certificate of appropriate grade pursuant to Title 23, California Code of Regulations, Division 4, Chapter 14, Section 3670 et. seq.


I, Harold J. Singer, Executive Officer, do hereby certify that the foregoing is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, Lahontan Region, on May 19, 1994.



HAROLD J. SINGER
EXECUTIVE OFFICER

- Attachments: A. Location Map
B. Treatment Plant Flow Schematics
C. Standard Provisions for Waste Discharge Requirement


Attachment "A"
Crestline Sanitation District
Wastewater Treatment Plants
Wastewater Disposal Sites



Page 1 of 4

LEGEND


1. HEADWORKS
2. OPERATIONS BUILDING
3. PRIMARY CLARIFICATION
4. TRICKLING FILTER
5. SECONDARY CLARIFICATION
6. RECIRCULATION PUMPS
7. SECONDARY SLUDGE PUMPS
8. CHLORINE CONTACT CHAMBER
9. SLUDGE HOLDING TANK
10. BELT FILTER PRESS
11. EMERGENCY STORAGE
12. SLUDGE STORAGE



HUSTON CREEK WASTEWATER TREATMENT PLANT

ATTACHMENT "B": TREATMENT PLANT FLOW SCHEMATICS

Page 2 of 4




LEGEND

1. HEADWORKS
2. OXIDATION DITCH
3. BRUSH AERATOR
4. SECONDARY CLARIFIER
5. CHLORINE CONTACT TANK
6. WET WELL & FINAL EFFLUENT PUMPS
7. OPERATIONS BUILDING
8. STAND-BY GENERATOR
9. SLUDGE PUMP STATION
10. LEVEL CONTROL STRUCTURE




N.T.S.



**CLEGHORN WASTEWATER
TREATMENT PLANT**

Attachment "B"
Rancho Las Flores Reclamation Area
Page 4 of 4



STANDARD PROVISIONS
FOR WASTE DISCHARGE REQUIREMENTS

1. Inspection and Entry

The discharger shall permit Regional Board staff:

- a. to enter upon premises in which an effluent source is located or in which any required records are kept;
- b. to copy any records relating to the discharge or relating to compliance with the waste discharge requirements;
- c. to inspect monitoring equipment or records; and
- d. to sample any discharge.

2. Reporting Requirements

- a. Pursuant to California Water Code 13267(b), the discharger shall immediately notify the Board by telephone whenever an adverse condition occurred as a result of this discharge; written confirmation shall follow within two weeks. An adverse condition includes, but is not limited to, spills of petroleum products or toxic chemicals, or damage to control facilities that could affect compliance.
- b. Pursuant to California Water Code Section 13260 (c), any proposed material change in the character of the waste, manner or method of treatment or disposal, increase of discharge, or location of discharge, shall be reported to the Regional Board at least 120 days in advance of implementation of any such proposal. This shall include, but not be limited to, all significant soil disturbances.
- c. The owners/discharger of property subject to waste discharge requirements shall be considered to have a continuing responsibility for ensuring compliance with applicable waste discharge requirements in the operations or use of the owned property. Pursuant to 13260(c), any change in the ownership and/or operation of property subject to the waste discharge requirements shall be reported to the Regional Board. Notification of applicable waste discharge requirements shall be furnished in writing to the new owners and/or operators and a copy of such notification shall be sent to the Regional Board.
- d. If a discharger becomes aware that any information submitted to the Regional Board is incorrect, the discharger shall immediately notify the Regional Board, in writing, and correct that information.
- e. Reports required by the waste discharge requirements, and other information requested by the Regional Board, must be signed by a duly authorized representative of the discharger.
- f. If the discharger becomes aware that their waste discharge requirements are no longer needed (because the project will not be built or the discharge will cease) the discharger shall notify the Regional Board in writing and request that their waste discharge requirements be rescinded.

3. Right to Revise Waste Discharge Requirements

The Board reserves the privilege of changing all or any portion of the waste discharge requirements upon legal notice to and after opportunity to be heard is given to all concerned parties.

4. Duty to Comply

Failure to comply with the waste discharge requirements may constitute a violation of the California Water Code and is grounds for enforcement action or for permit termination, revocation and reissuance, or modification.

5. Duty to Mitigate

The discharger shall take all reasonable steps to minimize or prevent any discharge in violation of the waste discharge requirements which has a reasonable likelihood of adversely affecting human health or the environment.

6. Proper Operation and Maintenance

The discharger shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) that are installed or used by the discharger to achieve compliance with the waste discharge requirements. Proper operation and maintenance includes adequate laboratory control, where appropriate, and appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities or similar systems that are installed by the discharger, when necessary to achieve compliance with the conditions of the waste discharge requirements.

7. Waste Discharge Requirement Actions

The waste discharge requirements may be modified, revoked and reissued, or terminated for cause. The filing of a request by the discharger for waste discharge requirement modification, revocation and reissuance, termination, or a notification of planned changes or anticipated noncompliance, does not stay any of the waste discharge requirements conditions.

8. Property Rights

The waste discharge requirements do not convey any property rights of any sort, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state or local laws or regulations.

9. Enforcement

The California Water Code provides for civil liability and criminal penalties for violations or threatened violations of the waste discharge requirements including imposition of civil liability or referral to the Attorney General.

10. Availability

A copy of the waste discharge requirements shall kept and maintained by the discharger and be available at all times to operating personnel.

11. Severability

Provisions of the waste discharge requirements are severable. If any provision of the requirements is found invalid, the remainder of the requirements shall not be affected.

12. Public Access

General public access shall be effectively excluded from treatment and disposal facilities.

13. Transfers


Providing there is no material change in the operation of the facility, this Order may be transferred to a new owner or operation. The owner/operator must request the transfer in writing and receive written approval from the Regional Board Executive Officer.

14. Definitions

- a. "Surface waters" as used in this Order, include, but are not limited to, live streams, either perennial or ephemeral, which flow in natural or artificial water courses and natural lakes and artificial impoundments of waters. "Surface waters" does not include artificial water courses or impoundments used exclusively for wastewater disposal.
- b. "Ground waters" as used in this Order, include, but are not limited to, all subsurface waters being above atmospheric pressure and the capillary fringe of these waters.

15. Storm Protection

All facilities used for collection, transport, treatment, storage, or disposal of waste shall be adequately protected against overflow, washout, inundation, structural damage or a significant reduction in efficiency resulting from a storm or flood having a recurrence interval of once in 100 years.



CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

MONITORING AND REPORTING PROGRAM NO. 94-57
WDID NO. 6B360106001

FOR

CRESTLINE SANITATION DISTRICT

San Bernardino County

I. MONITORING

✓ A. Flow Monitoring

	average	Peak
Houston Creek	0.7 MGD	2.5 MGD
SEELY Creek	0.5 MGD	1.0 MGD
CLEHORN	0.2 MGD	0.4 MGD

The Discharger shall monitor the following:

1. The total volume, in million gallons, of wastewater flow to each treatment facility for each day.
2. The total volume, in million gallons, of wastewater flow to each treatment facility for each month.
3. The average flow rate, in million gallons per day (mgd), of wastewater to each treatment facility calculated for each month.
4. The maximum instantaneous flow rate, in million gallons per day (mgd), of wastewater to each treatment facility that occurs each day.
5. The total volume, in million gallons, of wastewater flow to each disposal facility for each month.
6. The freeboard (distance from the top of the lowest part of the dike to the wastewater surface in the pond) measured each month in each surface impoundment. If a surface impoundment does not contain wastewater, indicate that it is empty.

B. Supply Water Monitoring

A chemical analysis of supply water which is representative of the municipal water used within the District's sewer area shall be performed twice annually, at approximate six-month intervals, and submitted to the Regional Board within 30 days of the analysis. The estimated volume (in millions of gallons) of water contributed to the sewer system by each municipal source shall be recorded for each semi-annual period. Municipal water samples for this analysis shall be collected within 7 days of the time effluent samples are collected. The chemical analysis shall include the following parameters:

<u>Parameter</u>	<u>Units</u>
Total Dissolved Solids	mg/l
Chloride	mg/l
Sodium	mg/l
Sulfate	mg/l

The following methods of obtaining a representation of the above chemical constituents in the municipal water will be considered acceptable:

1. Analyze a Composite Sample of the different water sources used in the sewerage area; the composite sample shall be weighted in proportion to the estimated semi-annual volume of water contributed to the sewer system by each municipal water source.
2. Perform a Mass Balance of the different water sources in the sewerage area; mathematically calculate the expected (mixed) constituent concentrations by using laboratory analyses of the constituent concentrations of the individual source waters, and estimated volumes of water contributed semi-annually to the sewer system from each water source.

C. Plant Effluent Monitoring

1. Beginning immediately, 24-hour composite samples of the effluent from the combined outfall for the wastewater treatment facilities shall be collected and analyzed to determine the magnitude of the following parameters:

<u>Parameter</u>	<u>Units</u>	<u>Frequency</u>
mean max 30, 45 • Biochemical Oxygen Demand •	mg/l	Twice per Month •
mean max 1, 2 • Chemical Oxygen Demand •	mg/l	Twice per Month •
• Methylene Blue Active Substances ¹	mg/l	Twice per Month •
(6 ≤ x ≤ 9) pH •	pH units	Twice per month •
• Oil & Grease •	mg/l	Twice per month •
• Kjeldahl Nitrogen •	mg/l as N	Monthly •
• Nitrate Nitrogen •	mg/l as N	Monthly •
• Ammonia Nitrogen •	mg/l as N	Monthly •
• Total Dissolved Solids	mg/l	Semiannually
• Chloride	mg/l	Semiannually
• Sodium	mg/l	Semiannually
• Sulfate	mg/l	Semiannually

¹ Testing shall also be performed at the outfall from each individual treatment plant.

<u>Parameter</u>	<u>Units</u>	<u>Frequency</u>
Boron	mg/l	Semiannually
Fluoride	mg/l	Semiannually
Total Cyanides	mg/l	Annually
Total Phenols	mg/l	Annually
Purgeable Organics*	mg/l	Annually
Base/Neutral/Acid Extractable Organics*	mg/l	Annually
Heavy Metals*	mg/l	Annually
Total Petroleum Hydrocarbons	mg/l	Annually

* Analysis shall be conducted for those substances included on the EPA list of priority pollutants and all other toxic substances known to be discharged to the Discharger's system using EPA test methods 603, 608, 624, 625, and other appropriate tests for heavy metals.

2. Beginning immediately, grab samples of chlorinated effluent discharged from each treatment plant, and the combined outfall at the reclamation site, shall be collected and analyzed to determine the magnitude of the following parameter:

<u>Parameter</u>	<u>Units</u>	<u>Frequency</u>
Total Coliform	MPN ²	Twice Weekly ³

D. Ground Water Monitoring

1. A system of ground water monitoring wells shall be located or installed in the vicinity of the reclamation site/Rancho Las Flores. The ground water monitoring system, at a minimum, shall include the following:
 - a. A minimum of three monitoring wells shall be installed or located such that the hydraulic gradient of the ground water may be determined. Existing ground water monitoring wells may be included in the total if the Discharger can verify that the following conditions are met:
 - (1) At least one well is located upgradient of the disposal area such that the ground water will not be impacted by the Discharger's waste discharges.
 - (2) At least two wells are located downgradient of the disposal area such that ground water potentially impacted by the Discharger's waste discharges will be monitored.

² Most Probable Number of Coliform Organisms per 100 ml of sample (MPN/100 ml)

³ Frequency of testing shall be increased to daily if disinfection standards in Section I.A.6. of the waste discharge requirements are not achieved.

- b. Additional wells shall be installed, if necessary, to ensure that the conditions (in 1.a.) above are met by the ground water monitoring system.
 - c. A report (for existing wells) or plan (for new wells) detailing the specific design and location of the wells shall be submitted to the Regional Board for review and approval by the Regional Board Executive Officer.
 - d. Ground water monitoring wells shall be installed in accordance with the approved plan, or verified to be in accordance with the above-mentioned conditions by January 1, 1995.
 - e. An as-built design report shall be submitted within 60 days after the ground water monitoring system is installed (or verified). This shall include a statement of certification signed by a California registered civil engineer or geologist regarding the placement, lithology and construction of the wells.
2. Ground water monitoring at existing monitoring wells (designated as Wells 1, 2, 3, and 4), and wells installed, or verified to be located in accordance with the above-mentioned conditions, shall be performed as described below. If existing monitoring wells are to be abandoned after new wells are approved and installed, at least 60 days prior to planned abandonment, the District must submit a plan detailing which wells are to be abandoned for approval by the Regional Board Executive Officer.
3. Beginning immediately, grab samples from the entire thickness or the upper 20 feet, whichever is less, of the uppermost ground water bearing zone shall be collected from the existing monitoring wells (and after January 1, 1995, any new wells) and analyzed to determine the magnitude of the following parameters:

<u>Parameter</u>	<u>Units</u>	<u>Frequency</u>
Sulfate	mg/l	Quarterly
Sodium	mg/l	Quarterly
Methylene Blue Active Substances	mg/l	Quarterly
Chloride	mg/l	Quarterly
Total Dissolved Solids	mg/l	Quarterly
Kjeldahl Nitrogen	mg/l	Quarterly
Ammonia Nitrogen	mg/l as N	Quarterly
Nitrate Nitrogen	mg/l as N	Quarterly
Purgeable Halocarbons*	µg/l	Annually
Purgeable Aromatics*	µg/l	Annually
Base/Neutral/Acid Extractable Organics*	µg/l	Annually

* Analysis shall be conducted for those substances included on the EPA list of priority pollutants and all other toxic substances known to be discharged to the Discharger's system using EPA test methods 603, 608, 624, 625, and other appropriate tests for heavy metals.

- a. The elevation (mean sea level), and depth below ground surface, of the ground water in each well shall be measured and recorded each time a monitoring well is sampled (prior to purging, as specified below).
- b. Well Purging: Ground water samples shall be collected only after at least three volumes of water in the well casing have been removed and temperature, electroconductivity, and pH of water in the well have stabilized.
- c. The velocity and direction of ground water flow under the disposal facility site shall be determined at least **annually** unless it can be shown that no changes have occurred.

✓ E. Sludge Monitoring

1. The Discharger shall submit a Sludge Management Plan Report by January 1, 1995.
2. The Discharger shall provide an explanation of any deviations from the Sludge Management Plan.
3. Total quantity of sludge generated (cleaned from any ponds) during the monitoring period.
4. Date and quantity of any sludge landfilled or removed off site, location of use, recipient (including name and address) and sludge disposal method (including crops grown, if appropriate) for all sludge moved offsite.

5. Cumulative total quantity of sludge currently stockpiled on site, including the quantity of sludge added to the stockpile during this monitoring period.
6. Laboratory analysis of sludge is not required at this time in recognition that there are no significant industrial waste inputs to the sewer system, and because sludge sampling is required by the disposal facility which accepts the Discharger's sludge. The Regional Board may require qualitative laboratory testing of sludge if sludge disposal practices and/or locations, as disclosed in the waste discharge requirements, are altered.

II. REPORTING

A. General Provisions

The Discharger shall comply with the "General Provisions for Monitoring and Reporting," dated July 1, 1993, which is attached to and made part of this Monitoring and Reporting Program.

B. Submittal Periods

Beginning on the 15th day of the month following the adoption of this Order, a monitoring report including the preceding information shall be submitted to the Regional Board. Subsequent monitoring reports shall be submitted to the Regional Board by the 15th day of the month following each quarter.

Ordered by: Harold J. Singer Dated: May 19, 1994
HAROLD J. SINGER
EXECUTIVE OFFICER

Attachment: General Provisions for Monitoring and Reporting

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
LAHONTAN REGION

GENERAL PROVISIONS FOR MONITORING AND REPORTING

1. SAMPLING AND ANALYSIS

- a. All analyses shall be performed in accordance with the current edition(s) of the following documents:
 - i. Standard Methods for the Examination of Water and Wastewater
 - ii. Methods for Chemical Analysis of Water and Wastes, EPA
- b. All analyses shall be performed in a laboratory certified to perform such analyses by the California State Department of Health Services or a laboratory approved by the Regional Board Executive Officer. Specific methods of analysis must be identified on each laboratory report.
- c. Any modifications to the above methods to eliminate known interferences shall be reported with the sample results. The method used shall also be reported. If methods other than USEPA approved methods or Standard Methods are used, the exact methodology must be submitted for review and must be approved by the Regional Board Executive Officer prior to use.
- d. The discharger shall establish chain-of-custody procedures to insure that specific individuals are responsible for sample integrity from commencement of sample collection through delivery to an approved laboratory. Sample collection, storage and analysis shall be conducted in accordance with an approved Sampling and Analysis Plan (SAP). The most recent version of the approved SAP shall be kept at the facility.
- e. The discharger shall calibrate and perform maintenance procedures on all monitoring instruments and equipment to ensure accuracy of measurements, or shall insure that both activities will be conducted. The calibration of any wastewater flow measuring device shall be recorded and maintained in the permanent log book.
- f. A grab sample is defined as an individual sample collected in fewer than 15 minutes.
- g. A composite sample is defined as a combination of no fewer than eight individual samples obtained over the specified sampling period at equal intervals. The volume of each individual sample shall be proportional to the discharge flow rate at the time of sampling. The sampling period shall equal the discharge period, or 24 hours, whichever period is shorter.

2. OPERATIONAL REQUIREMENTS**a. Sample Results**

Pursuant to California Water Code Section 13267(b), a copy of all sample results shall be available to the plant operator and/or Regional Board staff for inspection. The results shall be retained for a minimum of three years.

b. Operational Log

Pursuant to California Water Code Section 13267(b), an operation and maintenance log shall be maintained at the facility. All monitoring and reporting data shall be recorded in a permanent log book.

3. REPORTING

- a.** For every item where the requirements are not met, the discharger shall submit a statement of the actions undertaken or proposed which will bring the discharge into full compliance with requirements at the earliest time and submit a timetable for correction.
- b.** The discharger shall maintain all sampling and analytical results, including strip charts; date, exact place, and time of sampling; date analyses were performed; sample collector's name; analyst's name; analytical techniques used; and results of all analyses. Such records shall be retained for a minimum of three years. This period of retention shall be extended during the course of any unresolved litigation regarding this discharge or when requested by the Regional Board.
- c.** The discharger shall provide a brief summary of any operational problems and maintenance activities to the Board with each monitoring report. Any modifications or additions to, or any major maintenance conducted on, or any major problems occurring to the wastewater conveyance system, treatment facilities, or disposal facilities shall be included in this summary.
- d.** Monitoring reports shall be signed by:
 - i.** In the case of a corporation, by a principal executive officer at least of the level of vice-president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which the discharge originates;
 - ii.** In the case of a partnership, by a general partner;
 - iii.** In the case of a sole proprietorship, by the proprietor;

- iv. In the case of a municipal, state or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
- e. Monitoring reports are to include the following:
 - i. Name and telephone number of individual who can answer questions about the report.
 - ii. The Monitoring and Reporting Program Number.
 - iii. WDID Number.
- f. Annual Report

By January 30 of each year, the discharger shall submit an annual report to the Board with the following information:

- i. The compliance record and corrective actions taken or planned which may be needed to bring the discharge into full compliance with the discharge requirements.
- ii. Graphical and tabular data for the monitoring data obtained for the previous year.
- g. Modifications

This Monitoring and Reporting Program may be modified at the discretion of the Regional Board Executive Officer.

4. NONCOMPLIANCE

- a. Any person failing or refusing to furnish technical or monitoring reports or falsifying any information provided therein, is guilty of a misdemeanor and may be liable civilly in an amount of up to one thousand dollars (\$1,000) for each day of violation under Section 13268 of the Water Code.

1. The first part of the report deals with the general situation of the country and the progress of the work during the year. It is a summary of the work done and the results obtained. It is a general statement of the work done and the results obtained. It is a general statement of the work done and the results obtained.

2. The second part of the report deals with the specific work done during the year. It is a detailed statement of the work done and the results obtained. It is a detailed statement of the work done and the results obtained. It is a detailed statement of the work done and the results obtained.

3. The third part of the report deals with the financial statement of the work done during the year. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained.

4. The fourth part of the report deals with the conclusions drawn from the work done during the year. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained.

5. The fifth part of the report deals with the recommendations made for the future work. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained. It is a statement of the work done and the results obtained.